

NEXUS VALIDATION TEST PHASE 2.6

Network Hardware and Software version Details

DC 1 Image Versions

	Model No.	NVT 2.6
N7K	N7K-SUP1	6.2.6
N5K	N5K-C5548UP-SUP	5.2.1.N1.4
N3K	N3K-C3048TP-1GE-SUP	5.0.3.U5.1b
ASR9K	A9K-RSP-4G	4.2.3
C6K	VS-SUP2T-10G	150-1.SY3
	VS-S720-10G	122-33.SXJ4
	WS-SUP720	122-33.SXJ4
	WS-SUP32-GE	122-33.SXJ
C4K	WS-X45-SUP7-E	03.03.02.SG.151-1.SG2
	WS-C4948	150-2.SG6-6.9
UCS	UCS-5108	N/A
	UCS-B200-M2	2.1(2a)*
	UCS-B22-M3	2.1(2a)*
	UCS-2208XP-FEX	2.1(2a)*
	UCS-6296UP-FI	2.1(2a)*

DC 2 Image Versions

	Model No.	NVT 2.6
N7K	N7K-SUP2E	6.2.6
N5K	N5K-C5548P -SUP	5.2.1.N1.4
	N5K-C5548UP-SUP	5.2.1.N1.4
N3K	N3K-C3548P-10G-SUP	5.0.3.A1.2
ASR9K	A9K-RSP-4G	4.2.3
C6K	VS-SUP2T-10G	150-1.SY3
	VS-S720-10G	122-33.SXJ4
	WS-SUP720	122-33.SXJ4
C4K	WS-X45-SUP7-E	03.03.02.SG.151-1.SG2
	WS-C4948	150-2.SG6-6.9
UCS	UCS-5108	2.1(2a)*
	UCS-B200-M2	2.1(2a)*
	UCS-B22-M3	2.1(2a)*
	UCS-2208XP-FEX	2.1(2a)*
	UCS-6296UP-FI	2.1(2a)*

Caveats for NVT 2.6

<u>Assigned/New</u>	→	<i>Still working on fixes and may be seen in CCO image</i>
<u>Unreproducible</u>	→	<i>Not seen in CCO image, may be have fixed by other code fixes.</i>
<u>Verified/Resolved</u>	→	<i>Fixed in CCO image</i>
<u>Closed</u>	→	<i>System limitation and behavior will remain the same</i>

CSCuh90209/ CSCul48388

Symptom: ISSU gets stuck from 6.1.4.CCO to 6.2.5.55

Conditions: After initiating ISSU, ISSU gets stuck at the point where it extracts "cmp" version from system image of 6.2.5.55

Workaround: None

Severity: Severe

Status: Verified

Platform Seen: N7000

Resolved Releases: 6.2(6)

Applicable Releases:

CSCui61039

Symptom: N7700: XBAR ASIC interrupt errors when XBAR is inserted

Conditions: An N7706 chassis is powered up without any spines. Once the spines are inserted and LC's come up with traffic, then for each subsequently inserted spine, xbar asic interrupt errors are seen on the console

Workaround: None

Severity: Moderate

Status: Assigned

Platform Seen: N7700

Resolved Releases:

Applicable Releases: 6.2(6)

CSCuj56624

Symptom: OIL is not programmed in MFDM

Conditions: This may be seen in a multicast environment after a device reload.

Workaround: Issuing either of the below commands will fix this issue:
#clear ip mroute <multicast group ip> - on DR for a particular group

#clear ip mroute * - on DR for all groups

Severity: Severe
Status: Resolved
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCuj79031/ CSCuj95182

Symptom: n7k-sup2: /var/tmp location filled by diag_port_lb.6158 file
Conditions: On N7k loaded with 6.2.5.33_S1, these messages are seen: "N7K %\$ VDC-1 %\$ %SYSMGR-2-TMP_DIR_FULL: System temporary directory usage is unexpectedly high at 100% ". This issue is because of diag_port_lb file filling up /var/tmp location.
Workaround: None
Severity: Moderate
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCuj92558

Symptom: In a vpc+ setup running f2 cards as part of both vpc peer reload ,CFS errors are seen: 'sw-226-54 %\$ VDC-1 %\$ %L2FM-2-L2FM_CFS_SEND_FAILED: cfs send failed, num 2'
Conditions: l2fm is trying to send data over peer-link event before peer-link is declared up, which is causing the failure
Workaround: None
Severity: Moderate
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCuj95402

Symptom: ethpm cores on VDC reload on 6.2.5.33_S1
Conditions: N7k with sup1 has 3 vdc's, two vdc's are in fabricpath. After doing a reload of a fabricpath vdc, it failed to come online and ethpm cored.
Workaround: Not reproducible in the final images
Severity: Severe

Status: Unreproducible
Platform Seen: N7000
Resolved Releases:
Applicable Releases: 6.2(6)

CSCuj97300/ CSCul01126

Symptom: acqos cores seen with M-1 module failure after a switch reboot
Conditions: acqos crash seen on M1 module after switch is reloaded with 6.2(5.38)S0
Workaround: None
Severity: Moderate
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul06388

Symptom: ipqosmgr crashed while doing ISSU from 6.1.x to 6.2.6
Conditions: After doing ISSU from 6.1.x to 6.2.6, ipqosmgr core is seen on N7K
Workaround: None
Severity: Severe
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul16225

Symptom: When switches, one N7706 and one N7710 when running 6.2.5.45.S1 have diag failures on all modules
Conditions: Diags fail on modules with error: %DIAG_PORT_LB-2-REWRITE_ENGINE_LOOPBACK_TEST_FAIL: Module:2 Test:RewriteEngine Loopback failed 10 consecutive times. Faulty module:Module 5 Error:Loopback test failed. Packets possibly lost on the switch SUP fabric
Workaround: None
Severity: Severe
Status: Verified
Platform Seen: N7700
Resolved Releases: 6.2(6)

Applicable Releases:

CSCul18616

Symptom: Memory leaks observed in 'mtm' process on M1 module during MIB walks
Conditions: Memory leaks detected in 'mtm' process during MIB walk of CiscoProcessMIB and CiscoCBQoS
Workaround: Not reproducible in the final images
Severity: Minor
Status: Unreproducible
Platform Seen: N7000
Resolved Releases: None
Applicable Releases: 6.2(6)

CSCul20672/ CSCul81685

Symptom: ISSD Fails from 6.2.5.65.S2 to 6.2.2a with service vdc_mgr error.
Conditions: ISSD of 6.2.6 --> 6.2.2/6.2.2a - if "f3" shows up in either "limit-resource module-type" or "system module-type", then ISSD will abort with error: VDC_MGR has detected a potential issue and blocked upgrade (0x413C0017)(vdc: 1). System detected f3 in switchwide VDC mode("system module-type"), which is not supported in the version you are downgrading to. Please remove f3 from the relevant config before the downgrade"
Workaround: None
Severity: Moderate
Status: Resolved
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul26450

Symptom: rpm core seen during 'copy r s vdc-all', config copy is aborted
Conditions: After setting the boot string and doing a 'copy r s vdc-all' on N7700, rpm core is seen. Config copy is aborted after the core: %SYSMGR-2-SERVICE_CRASHED: Service "rpm" (PID 7647) hasn't caught signal 6 (core will be saved). %SYSMGR-2-CFGWRITE_ABORTED: Configuration copy aborted.
Workaround: None
Severity: Moderate
Status: Resolved
Platform Seen: N7700
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul28020

Symptom: "plugin" core is seen after "copy r s" is done on 6.2.5.48.S0 - N7K
Conditions: plugin core was seen on N7K, running version 6.2.5.48_S0. The core was seen after these series of steps: (1) Loading 6.2.5.48_S0 (previously running 6.2.5.33_S2) and doing a couple of system switchovers. (2) After 2nd switchover a "copy r s" was done (3) 'plugin' cored
Workaround: None
Severity: Severe
Status: Unreproducible
Platform Seen: N7000
Resolved Releases:
Applicable Releases:

CSCul30416

Symptom: ISSD Failure: Workaround suggested by NX-OS not working
Conditions: After initiating ISSD from 6.2.5.48 (S0) to 6.2.2.S42, pre-upgrade check fails with error which in-turn aborts the ISSD: Return code 0x41A10008 (Config check failure). Service "pltfm_config" in vdc 1: 'rate-limiter otv and/or netflow is configured for module <mod>'.This is not supported in the target version. Please issue the 'no hardware rate-limiter command to remove the module rate-limiters'
Workaround: Need to disable netflow & otv at hardware level. Command: N7K(config)# no hardware rate-limiter layer-2 netflow disable module x
Severity: Moderate
Status: Closed
Platform Seen: N7000
Resolved Releases: None
Applicable Releases: 6.2(6)

CSCul34953/ CSCul36654

Symptom: Packet loss will be seen after ISSU from 6.1.4/6.1.4a to 6.2.5.52.S0 on N7K
Conditions: After doing ISSU from 6.1.4/6.1.4a to 6.2.5.52.S0 image, ping between directly connected interfaces and also MGMT interface doesn't work due to which there is traffic loss.
Workaround: None
Severity: Severe
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul44598

Symptom: Intermittent traffic loss for hosts with spt-threshold infinity configured in a network which also has sparse mode hosts
Conditions: This issue is seen when the Host with spt-threshold infinity and the sparse mode host have the common intermediate router which is in the shared tree path for both the hosts and also in the (S, G, R) prune path from the sparse mode host while it sends joins to the source tree
Workaround: Make shared tree and source tree the same path for the sparse mode host or have spt-threshold infinity hosts only
Severity: Severe
Status: Assigned
Platform Seen: N7000
Resolved Releases:
Applicable Releases: 6.2(6)

CSCul47945

Symptom: On SSO xlated vlan's LPSS Stale entry on old-stdby causes traffic loss
Conditions: The problem is that in this case, STP queries Vlan-mgr's LPSS to find out vlan translation information. Currently Vlan-mgr's LPSS on standby is build when the switchover is completed and when it is restoring its state from PSS. However, during switchover, STP comes up before Vlan-mgr and starts sending BPDUs. Since the LPSS is not build till that time, first few BPDUs don't have information of translated vlan and therefore it causes traffic loss for few seconds, till LPSS is build.
Workaround: None
Severity: Severe
Status: Resolved
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul66808

Symptom: isis_fabricpath cores while doing ISSD from 6.2.5.60.S2 to 6.2.2
Conditions: ISSD was done on N7K from 6.2.5.60_S2 to CCO 6.2.2 image (sup2). N7K has 2 vdc's in fabricpath. isis_fabricpath cored on these vdc's after system switchover was done.
Workaround: None
Severity: Severe
Status: Verified
Platform Seen: N7000
Resolved Releases: 6.2(6)
Applicable Releases:

CSCul88464

Symptom: ISSU aborts occasionally with timeout error

Conditions: Occasionally while testing ISSU from 5.2.9 - CCO image to 6.2.5.65.S2/6.2.5.60.S2 image, ISSU aborts with timeout error, however on re-issue of ISSU command, it runs smooth and ISSU completes successfully

Workaround: Re-issue the ISSU command "install all kickstart <kickstart_image> system <system_image>"

Severity: Minor

Status: New

Platform Seen: N7000

Resolved Releases:

Applicable Releases: 6.2(6)

CSCul98066

Symptom: Standby SUP fails to come online with correct image during ISSU.

Conditions: ISSU to image 6.2.6.S1 from 5.2.9/6.1.4 fails because standby SUP fails to come online with 6.2.6.S1 after reload, returning error: Install has failed. Return code 0x40930040 (standby supervisor booted up with unexpected version)

Workaround: None

Severity: Severe

Status: Duplicate of CSCul47945

Platform Seen: N7000

Resolved Releases: 6.2(6)

Applicable Releases:

DC1 test results

			NVT 2.6	
Heading	Test Case	Pass/Fail Verification		
1. DC1 Setup	DC1 Setup			
1.1. Common Configuration	Common Configuration for all switches	Verify SSH works through the management network on a dedicated vrf Verify Tacacs+ (tacacs.interop.cisco.com) and primary/backup servers Verify NTP and Time Zone : ntp.interop.cisco.com Verify Syslog to syslog.interop.cisco.com Verify DNS domain : interop.cisco.com and server : 172.28.92.9-10 Verify DNS search list: interop.cisco.com, cisco.com Verify CMP port connections to the management network. Verify CDP neighbors Verify SNMP agent (read community): public + interop; (private community): private + cisco Verify SNMP traps to monitor network events Verify UDLD neighbors and UDLD aggressive mode Verify LACP for link aggregation Verify BFD peering for all possible clients with default protocol timers for the clients on all relevant interfaces. Verify SSO/NSF and GR Verify CoPP function Verify SPAN ensuring cross-module SPAN. Configure Authentication for: OSPF/OSPFv3, HSRP/HSRPv6, MSDP, Layer 2 ISIS (FabricPath, OTV) Verify DHCP IP helper and primary/backup server	pass	
1.2. Edge/Core to Public Network Setup				
1.2.1. DC1-Core-N7k-1	Setup interfaces from DC1-Core-N7k-1 to Public network [AS1-1,AS1-2]	BGP: Verify Ipv4 eBGP peering between DC1-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath. BGP: Verify Ipv6 eBGP peering between DC1-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath. PIM: Verify PIM peering. Redistribute: Verify routes are redistributed according to configured policies. Acl: Verify ACL policies are properly programmed in hardware and are functioning as expected.	pass	

		<p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p> <p>For each feature enable label sharing and ensure it is actually deployed by checking the number of used TCAM entries (identify all the features that share labels).</p>		
		Verify bank chaining of the TCAM.		
1.2.2. DC1-Core-N7k-2	Setup interfaces from DC1-Core-N7k-2 to Public network [AS1-1,AS1-2]	<p>BGP: Verify IPv4/IPv6 eBGP peering between DC1-Core-n7k-2 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>BGP: Verify Ipv6 eBGP peering between DC1-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>PIM: Verify PIM peering.</p> <p>Redistribute: Verify routes are redistributed according to configured policies.</p> <p>Acl: Verify ACL policies are properly programmed in hardware and are functioning as expected.</p> <p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p> <p>For each feature enable label sharing and ensure it is actually deployed by checking the number of used TCAM entries (identify all the features that share labels).</p> <p>Verify bank chaining of the TCAM.</p>	pass	
1.2.3. DC1-Core-ASR9k-3	Setup interfaces from DC1-Core-ASR9k-3 to Public network [AS1-1,AS1-2]	<p>BGP: Verify IPv4/IPv6 eBGP peering between DC1-Core-ASR9k-3 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>BGP: Verify Ipv6 eBGP peering between DC1-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>PIM: Verify PIM peering.</p> <p>Redistribute: Verify routes are redistributed according to configured policies.</p> <p>Acl: Verify ACL policies are functioning as expected.</p> <p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p>		
1.3. Core to Distribution Setup				
1.3.1. DC1-Core-N7k-1	Setup interfaces from DC1-Core-N7k-1	OSPF: Verify OSPFv2/OSPFv3 peering.	pass	

	to Distribution blocks	PIM: Verify PIM peering. MSDP: Verify MSDP peering and SA-cache		
1.3.2. DC1-Core-N7k-2	Setup interfaces from DC1-Core-N7k-2 to Distribution blocks	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. MSDP: Verify MSDP peering and SA-cache	pass	
1.3.3. DC1-Core-ASR9k-3	Setup interfaces from DC1-Core-ASR9k-3 to Distribution blocks	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. MSDP: Verify MSDP peering and SA-cache		
1.4. Distribution to Core Setup				
1.4.1. DC1-Dist-N7k-101	Setup interfaces from Distribution N7k to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. OTV: Verify OTV ISIS adjacencies are properly established and OTV routing table. Verify the primary AS is being used. On the primary AS, verify all edge devices show up in the unicast replication list using "show otv adjacency-server replication-list".	pass	
1.4.2. DC1-Dist-N7k-102	Setup interfaces from Distribution N7k to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. OTV: Verify OTV ISIS adjacencies are properly established and OTV routing table. Verify the primary AS is being used. On the primary AS, verify all edge devices show up in the unicast replication list using "show otv adjacency-server replication-list".	pass	
1.4.3. Distribution Interop				
1.4.3.1. DC1-Dist-C6kE8-103-VSS	Setup interfaces from Distribution C6kE8 VSS to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering.	pass	
1.4.3.2. DC1-Dist-C6kE8-104	Setup interfaces from Distribution C6kE8 to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering.	pass	
1.4.3.3. DC1-Dist-C6kE7-105-VSS	Setup interfaces from Distribution C6kE7 VSS to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering.	pass	
1.4.3.4. DC1-Dist-C6kE7-106	Setup interfaces from Distribution C6kE7 to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering.	pass	

1.4.3.5. DC1-Dist-C4k-107	Setup interfaces from Distribution C4k to the core switches	OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering.	pass	
1.5. Distribution to ToR Setup				
1.5.1. DC1-Dist-N7k-101	Setup interfaces from Distribution N7k to the ToR	vPC: Verify vPC peer-gateway, vPC peer-switch, vPC Object tracking, vPC auto recovery. Verify vPC peer status, vPC priority and consistency parameters. Check MAC/ARP/igmp snooping synchronization. OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. MSDP: Verify MSDP peering and SA-cache IGMP/MLD Snooping: Verify IGMP/MLD Snooping HSRP: Verify HSRP Ipv4/IPv6 peering between s5 and s6. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch. STP: Verify RSTP parameters and port status. ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines. ACL: Verify that all the policies are properly programmed in hardware. QoS: Verify QoS marking. DHCP Relay Agent: Verify DHCP relay functionality. BOOTP: Verify BOOTP functionality. OTV: Verify OTV AS adjacencies state and verify VLAN load-balancing for each of the OTV edge devices. Verify remote MAC learning in the OTV MAC table.	pass	
1.5.1.1. ToR FEX vPC	Setup interface from DC1-Dist-N7k-101 to ToR FEX vPC	Verify FEX association with configured port-channels and that the FEX devices are up.	pass	
1.5.1.2. ToR Layer 2 Switch	Setup interface from DC1-Dist-N7k-101 to ToR Layer 2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.1.3. ToR N5k vPC	Setup interface from DC1-Dist-N7k-101 to ToR N5k vPC	Verify vPC status and consistency parameters. Verify spanning tree status on all vlans.	pass	
1.5.1.4. ToR UCS Fabric Interconnect vPC	Setup interface from DC1-Dist-N7k-101 to ToR Fabric Interconnect vPC	Verify vPC status and consistency parameters		
1.5.2. DC1-Dist-N7k-102	Setup interfaces from Distribution N7k to the ToR	FabricPath: Verify FabricPath route and mac-table are built as expected. Verify IS-IS database. Verify multi-destination trees for unknown unicast, broadcast and multicast with root configured on the spine switches. Verify fabricpath load-balance works as expected OSPF: Verify OSPFv2/OSPFv3 peering. PIM: Verify PIM peering. MSDP: Verify MSDP peering and SA-cache IGMP/MLD Snooping: Verify IGMP/MLD Snooping	pass	

			<p>HSRP: Verify HSRP Ipv4/IPv6 peering between s51 & s52; s53 & s54. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch with G flag.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP: Verify BOOTP functionality.</p> <p>OTV: Verify OTV AS adjacencies state and verify VLAN load-balancing for each of the OTV edge devices. Verify remote MAC learning in the OTV MAC table.</p>		
1.5.2.1.	ToR FEX	Setup interface from distribution DC1-Dist-N7k-102 to ToR FEX	Verify FEX association with configured port-channels and that the FEX devices are up.	pass	
1.5.2.2.	ToR Layer 2 Switch	Setup interface from DC1-Dist-N7k-102 to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.2.3.	ToR N5k FabricPath	Setup interface from DC1-Dist-N7k-102 to ToR N5k FabricPath	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify the unknown unicast, broadcast and multicast multi-destination trees are built as expected.</p> <p>Verify fabricpath load-balance works as expected</p> <p>Verify IS-IS database, topology and route distribution.</p>	pass	
1.5.2.4.	ToR UCS Fabric Interconnect vPC+	Setup interface from DC1-Dist-N7k-102 to ToR Fabric interconnect vPC+	Verify vPC+ status and consistency parameters.		
1.5.2.5.	ToR Layer 2 Switch vPC+	Setup interface from DC1-Dist-N7k-102 to ToR L2 Switch vPC+	Verify vPC+ status and consistency parameters.	pass	
1.5.2.6.	ToR N3k Layer 3	Setup interface from DC1-Dist-N7k-102 to ToR N3k Layer 3	<p>Verify OSPF/OSPFv3 peering.</p> <p>Verify PIM peering.</p>	pass	
1.5.3.	Distribution Interop				
1.5.3.1.	DC1-Dist-C6kE8-103-VSS	Setup interfaces from Distribution DC1-Dist-C6kE8-103-VSS to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>VSS: Verify VSS active/standby roles and VSL/MEC status. Verify Fast-redirect optimization</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP configuration.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p>	pass	

			<p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
1.5.3.1.1.	ToR Layer	Setup interface from DC1-Dist-C6kE8-103-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.3.1.2.	ToR UCS Fabric Interconnect	Setup interface from DC1-Dist-C6kE8-103-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
1.5.3.2.	DC1-Dist-C6kE8-104	Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
1.5.3.2.1.	ToR Layer	Setup interface from DC1-Dist-C6kE8-104 to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.3.2.2.	ToR UCS Fabric Interconnect MEC	Setup interface from DC1-Dist-C6k-006-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
1.5.3.2.3.	ToR N5k MEC	Setup interface from DC1-Dist-C6kE8-104 to ToR N5k MEC	Verify spanning tree status on all vlans.	pass	
1.5.3.2.4.	ToR N3k Layer 3	Setup interface from DC1-Dist-C6kE8-104 to ToR N3k Layer 3	<p>Verify OSPF/OSPFv3.</p> <p>Verify PIM peering.</p>	pass	
1.5.3.3.	DC1-Dist-C6kE7-105-VSS	Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>VSS: Verify VSS active/standby roles and VSL/MEC status. Verify Fast-redirect optimization</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p>	pass	

			<p>HSRP: Verify HSRP configuration.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
1.5.3.3.1.	ToR Layer 2 Switch	Setup interface from DC1-Dist-C6kE7-105-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.3.3.2.	ToR UCS Fabric Interconnect	Setup interface from DC1-Dist-C6kE7-105-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
1.5.3.4.	DC1-Dist-C6kE7-106	Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
1.5.3.4.1.	ToR Layer 2 Switch	Setup interface from DC1-Dist-C6kE8-008-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
1.5.3.4.2.	ToR UCS Fabric Interconnect MEC	Setup interface from DC1-Dist-C6kE7-106 to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
1.5.3.4.3.	ToR N5k MEC	Setup interface from DC1-Dist-C6kE7-106 to ToR N5k MEC	Verify spanning tree status on all vlans.	pass	
1.5.3.5.	DC1-Dist-C4k-107	Setup interfaces from Distribution C4k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p>	pass	

		<p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
1.5.3.5.1. ToR UCS Fabric Interconnect	Setup interface from DC1-Dist-C4k-107 to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
1.6. ToR to Distribution Setup				
1.6.1. ToR Layer 2 Switch vPC				
1.6.1.1. DC1-Dist-N7k-101	Setup vPC interface from ToR Layer 2 Switch to DC1-Dist-N7k-101	<p>STP: Verify RSTP parameters and port status.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
1.6.2. ToR Layer 2 Switch vPC+				
1.6.2.1. DC1-Dist-N7k-102	Setup interfaces from ToR Layer 2 Switch vPC+ to the DC1-Dist-N7k-102	<p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
1.6.3. ToR N3k Layer 3				
1.6.3.1. DC1-Dist-N7k-102	Setup interface from ToR N3k Layer 3 to DC1-Dist-N7k-102	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p>	pass	

			BOOTP Relay Agent: Verify BOOTP relay functionality.		
1.6.3.2.	DC1-Dist-C6kE8-104	Setup interface from ToR N3k Layer 3 to DC1-Dist-C6kE8-104	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
1.6.4.	ToR N5k vPC				
1.6.4.1.	DC1-Dist-N7k-101	Setup interface from ToR N5k vPC Switch to DC1-Dist-N7k-101	<p>vPC: Verify vPC peer status and consistency parameters. Check MAC/ARP/igmp snooping synchronization.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
1.6.5.	ToR N5k FabricPath				
1.6.5.1.	DC1-Dist-N7k-102	Setup interfaces from ToR N5k FabricPath to the DC1-Dist-N7k-102	<p>FabricPath: Verify FabricPath route and mac-table are built as expected. Verify IS-IS database. Verify multi-destination trees for unknown unicast, broadcast and multicast. Verify fabricpath load-balance works as expected</p> <p>HSRP: Verify HSRP MAC address is programmed in the mac table</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
1.7.	ToR to Hosts Setup				
1.7.1.	FEX				
1.7.1.1.	End Host	Setup interface from FEX to End Host (traffic generator)	<p>Verify spanning tree status (edge) on all vlans for the host ports.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>	pass	
1.7.1.2.	End Host vPC	Setup interface from FEX to End Host vPC (traffic generator)	<p>Verify spanning tree status (edge) on all vlans for the host ports.</p> <p>Verify mac table is populated correctly.</p>	pass	

		Verify IGMP/MLD snooping.		
1.7.1.3. UCS Fabric Interconnect	Setup interface from FEX to UCS Fabric Interconnect	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.1.4. UCS Fabric Interconnect vPC	Setup interface from FEX to UCS Fabric Interconnect vPC	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.1.5. UCS Fabric Interconnect vPC+	Setup interface from FEX to UCS Fabric Interconnect vPC+	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.2. ToR Layer 2 Switch				
1.7.2.1. End Host	Setup interface from ToR Layer 2 Switch to End Host (traffic generator)	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
1.7.2.2. UCS Fabric Interconnect	Setup interface from ToR Layer 2 Switch to UCS Fabric Interconnect	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.3. ToR N3k Layer 3				
1.7.3.1. End Host	Setup interface from ToR N3k Layer 3 Switch to End Host (traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
1.7.4. ToR N5k vPC				
1.7.4.1. FEX vPC	Setup interface from ToR N5k FEX to End Host vPC (traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
1.7.4.1. UCS Fabric Interconnect vPC	Setup interface from ToR N5k vPC to UCS Fabric Interconnect vPC	Verify spanning tree status on all vlans. Verify mac table is populated correctly.		

		Verify IGMP/MLD snooping.		
1.7.5. ToR N5k Fabricpath Leaf				
1.7.5.1. UCS Fabric Interconnect vPC+	Setup interface from ToR N5k FP to UCS Fabric Interconnect vPC+	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.5.2. End Host vPC+	Setup interface from ToR N5k FP to End Host vPC+ (Traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.5.3. End Host	Setup interface from ToR N5k FP to End Host (Traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.7.5.4. ToR L2 switch	Setup interface from ToR N5k FP to ToR L2 switch	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
1.7.5.5. ToR L2 switch vPC+	Setup interface from ToR N5k FP to ToR L2 switch vPC+	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
1.7.5.6. FEX vPC+	Setup interface from N5k FP ToR FEX vPC+ to End Hosts (Traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
1.8. UCS Setup				
1.8.1. Fabric Interconnect				
1.8.1.1. DC1-Dist-N7k-101				
1.8.1.1.1. UCS to N7K FEX	Setup for UCS 6296UP FI to FEX	Verify the two FI's are in a cluster. Verify FI end host mode configuration. Verify uplink port-channels towards FEX. Verify static pinning on the FI uplinks.	pass	

			Verify IOM to FI connectivity and pinning.		
1.8.1.1.2.	UCS to N7K VPC	Setup for UCS 6296UP FI to FEX	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards ToR FEX.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.1.3.	UCS to Layer 2 Switch	Setup for UCS 6296UP FI to Layer 2 Switch	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards layer 2 switch.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and pinning.</p>	pass	
1.8.1.1.4.	UCS to N5k VPC	Setup for UCS 6248UP FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.1.5.	UCS to N7K FEX VPC	Setup for UCS 6248UP FI to N7K FEX VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N7k VPC.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.1.6.	UCS to N5K FEX VPC	Setup for UCS 6296UP FI to N5K FEX VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N7k VPC.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.2.	DC1-Dist-N7k-102				

1.8.1.2.1. UCS to N7K FabricPath VPC+	Setup for UCS 62xx FI to N7k FabricPath VPC+	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N7k VPC+.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.2.2. UCS to Layer 2 Switch	Setup for UCS 6248UP FI to Layer 2 Switch	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards the layer 2 switch.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.2.3. UCS to N5K FabricPath VPC+	Setup for UCS 6248UP/6296UP FI to N5k VPC+	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC+.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.2.4. UCS to N5K FEX FabricPath VPC+	Setup for UCS 6296UP FI to N5k FEX VPC+	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC+.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>	pass	
1.8.1.3. DC1-Dist-C6kE8-103-VSS				
1.8.1.3.1. UCS to C6kE8 VSS	Setup for UCS 6248UP FI to C6kE8 VSS	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.4. DC1-Dist-C6kE8-104 Standalone				

1.8.1.4.1. UCS to C6kE8 Standalone	Setup for UCS 62xx FI to C6kE8 Standalone	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.4.2. UCS to N5k VPC	Setup for UCS 62xx FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.5. DC1-Dist-C6kE7-105-VSS				
1.8.1.5.1. UCS to C6kE7 VSS	Setup for UCS 62xx FI to C6kE7 VSS	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.6. DC1-Dist-C6kE7-106 Standalone				
1.8.1.6.1. UCS to C6kE7 Standalone	Setup for UCS 6248UP FI to C6kE7 Standalone	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.1.6.2. UCS to N5k VPC	Setup for UCS 62xx FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		

1.8.1.7. DC1-Dist-C4k-107				
1.8.1.7.1. UCS to C4k	Setup for UCS 62xx FI to C4k	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C4k.</p> <p>Verify static pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
1.8.2. UCS Setup				
1.8.2.1 UCSM Initial Configuration	<p>Setup network parameters for the FI cluster.</p> <p>-</p>	<p>Verify that the primary FI's System Name, Admin Password, Management IP Address, Management IP Netmask, Default Gateway, DNS Server IP, and Domain Name are all properly configured.</p> <p>Verify that the secondary FI is configured to be in a cluster.</p> <p>Verify that the FI cluster is reachable.</p> <p>Verify successful user authentication.</p>		
1.8.2.2. Hypervisor Installation	Setup ESXi 5.1 for server virtualization	<p>Verify the ESXi 5.1 software installation on the B2xx Mx blade.</p> <p>Verify server's IP address can be pinged.</p> <p>Verify the configured VM's are up and running.</p> <p>Verify the distributed virtual switch is functional.</p> <p>Verify successful installation of operating systems.</p> <p>Verify traffic can be generated by the servers.</p>		
1.8.2.3 VM Provisioning	Configure 5 virtual machines with 10 virtual network adapters [per each ESXi host].	<p>Verify through the VM's CLI that the virtual network interfaces are up and associated to a vNIC on UCSM.</p> <p>Verify through the VM's CLI and vCenter 5.1, that the proper MAC addresses are associated to each of the VM's virtual network interfaces.</p> <p>Verify through the VM's CLI and vCenter 5.1, that the proper IP addresses are associated to each of the VM's virtual network interfaces via DHCP.</p> <p>Verify that the VMs are able to be accessed through SSH/Telnet.</p> <p>Verify that the VMs are reachable through the management interface.</p> <p>Verify that the VMs in the same subnet are reachable with one another.</p>		
1.8.2.4. VM-FEX Installation	<p>Setup VM-FEX</p> <p>Create datacenter in UCSM under VM tab</p>	<p>Verify through UCSM and vCenter that VM-FEX port profiles are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p>		

	<p>Create folder under datacenter in UCSM</p> <p>Create distributed virtual switch under folder in UCSM.</p>	<p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters via DHCP. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved. Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode. Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved. Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode. Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved. Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode. Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>		
<p>1.8.2.4. Nexus 1000V Installation (Pod 106)</p>	<p>Setup Nexus 1000V</p>	<p>Verify that the Nexus 1000V is installed following the Java Installer procedure.</p>		

Configure uplink port profile on the Nexus 1000V

Verify the network configurations for control, packet and management ports are configured with the proper vlans.
Verify the configured VEMs and VSMS are up and running.
Verify that the VSMS are properly configured in cluster-mode.
Verify the n1kv distributed virtual switch is functional.
Verify successful installation of operating systems.
Verify traffic can be generated by the servers.
Verify through UCSM and vCenter that all port profiles are properly mapped to the network adapters in standard performance mode.
Verify that vCenter executes the command properly and that it is reflecting the proper operation.
Using the NXOS CLI, Verify that the operation is properly updated during the entire process.
Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.
Verify the configured VEMs and VSMS are up and running.
Verify that the VSMS are properly configured in cluster-mode.
Verify through UCSM and vCenter that all port profiles are properly mapped to the network adapters in standard performance mode.
Fault monitoring verification on vCenter and NXOS CLI.
Verify the expected behavior is properly executed following the best practice and user guide.
Verify that vCenter executes the command properly and that it is reflecting the proper operation.
Using the NXOS CLI, Verify that the operation is properly updated during the entire process.
Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.
Verify the configured VEMs and VSMS are up and running.
Verify that the VSMS are properly configured in cluster-mode.
Verify through UCSM and vCenter that all port profiles are properly mapped to the network adapters in standard performance mode.
Fault monitoring verification on vCenter and NXOS CLI.
Verify the expected behavior is properly executed following the best practice and user guide.
Verify that vCenter executes the command properly and that it is reflecting the proper operation.
Using the NXOS CLI, Verify that the operation is properly updated during the entire process.
Verify that the configured VEMs and VSMS are up and running.
Verify that the VSMS are properly configured in cluster-mode.

Configure server-side port profiles on the Nexus 1000V

Configure ESXi hosts to use the Cisco Nexus 1000V in vCenter 5.1

	Associate ESXi hosts to use the Cisco Nexus 1000V in vCenter 5.1	<p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify through UCSM and vCenter that all port profiles are properly mapped to the network adapters in standard performance mode. Fault monitoring verification on vCenter and NXOS CLI.</p> <p>Verify the expected behavior is properly executed following the best practice and user guide.</p> <p>Verify that vCenter executes the command properly and that it is reflecting the proper operation.</p> <p>Using the NXOS CLI, Verify that the operation is properly updated during the entire process.</p> <p>Verify that the configured VEMs and VSMS are up and running.</p> <p>Verify that the VSMS are properly configured in cluster-mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify through UCSM and vCenter that all port profiles are properly mapped to the network adapters in standard performance mode. Fault monitoring verification on vCenter and NXOS CLI.</p> <p>Verify the expected behavior is properly executed following the best practice and user guide.</p>		
2. Network Disruptions Test Cases	Network Disruptions Test Cases Common checks for all network disruptions	<p>Verify that MEM and CPU Usage for Supervisors and line cards are comparable to previous releases.</p> <p>Verify that all unicast/multicast traffic convergence is comparable to previous releases.</p> <p>Verify UCS end host mode on FI and VM-FEX functionality.</p>		
2. Network Disruptions Test Cases	Network Disruptions Test Cases Common checks for all network disruptions	<p>Verify that MEM and CPU Usage for Supervisors and line cards are comparable to previous releases.</p> <p>Verify that all unicast/multicast traffic convergence is comparable to previous releases.</p> <p>Verify UCS end host mode on FI and VM-FEX functionality.</p> <p>Verify UCS unicast/multicast traffic convergence</p>		
2.1. L2 Link Failure/Recovery	L2 Port-channel Failure/Recovery between Distribution and ToR devices	<p>Verify STP port states after link disruption are in the expected forwarding mode. Verify that the STP root does not change.</p> <p>Verify HSRP peers status does not change. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify the L2 forwarding table should remove entries of the affected link at the access switch and re-learn correctly on the alternative link.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p>	pass	

<p>L2 port-channel member failure/recovery between Distribution and ToR devices</p>	<p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that the L2 forwarding entries on all switches for nodes connected to the access layer are associated with the corresponding STP forwarding ports.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the routers.</p> <p>Verify ACL TCAM is programmed correctly to share for ACL's and features that allow for sharing and verify ACL's are not sharing when not expected.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify isolated vlans remain to have complete separation from other ports within the same PVLAN but not from the promiscuous ports using proxy-arp.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify that IPv6 global HSRP is functional.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify port-channel load balancing and rbh assignment</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast will be proportionate to number of members failed</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>
<p>vPC leg failure/recovery between Distribution and ToR devices</p>	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC leg is shut.</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>

	<p>vPC leg member failure/recovery between Distribution and ToR devices</p>	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC leg member is shut (assuming there are 2 members on each vPC leg).</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	pass
	<p>vPC peer-link failure/recovery between Distribution vPC peer switches</p>	<p>Verify that the operational secondary vPC peer will bring down the vPC member ports.</p> <p>Verify that secondary peer will suspend the vpc vlan svi's.</p> <p>Verify that on recovery, the original states will be re-established.</p>	pass
	<p>vPC Peer-keepalive failure/recovery between Distribution vPC peer switches</p>	<p>There is no expected effects, both vPC peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>Verify that on recovery, the original states will be re-established.</p>	pass
	<p>vPC peer-link and keep-alive failure between Distribution vPC peer switches</p>	<p>If the keep-alive fails first followed by vPC peer link, then both vPC peers will become active. Verify dual-active scenario is encountered and with the peer-switch feature enabled, ensure the downstream device does not detect any spanning-tree misconfigurations.</p> <p>If the vPC peer-link fails first followed by the keep-alive link, the secondary should keep it's vPC member ports suspended.</p> <p>With vPC auto-recovery configured if the vPC peer-link fails first followed by the keep-alive link, the secondary will keep it's vPC member ports suspended for the duration of three consecutive keepalive failures. After the timer expires the member ports will be unsuspending and the system will change role to primary causing Dual-active scenario.</p>	pass
	<p>vPC peer-link and keep-alive recovery from Dual-active between Distribution vPC peer switches</p>	<p>If keep-alive is recovered first, the active/secondary switch is determined by the role priority and the secondary switch will suspend vPC member ports and vpc svi's.</p> <p>If vpc peer link is recovered first followed by keep alive, the active/secondary switch is determined by the role priority and the system resumes.</p>	pass
	<p>OTV VDC L2 Link Failure/Recovery</p>	<p>Verify traffic will recover after link recovery.</p>	
2.2. L3 Link Failure/Recovery	<p>L3 Port-channel Failure/Recovery between Edge and Public Network[Interop between N7K, C6K]</p>	<p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify BGP multi-path load-balancing.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p>	pass

L3 Port-channel Failure/Recovery
between Core and Distribution
Layers[Interop between N7K, ASR9k,
C6K, C4k]

Verify BGP reconvergence (control-plane & data-plane).
Verify PIM neighbor status.
Verify GRE Tunnel re-route due to transport disruption.
Verify MTU fragmentation and reassembling at tunnel edge.
Verify AutoRP mapping and boundaries.
Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.
Verify the L2 forwarding table should remove entries of the affected link.
Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.
Verify SPAN is mirroring packets correctly.
Verify OTV traffic reconverges and optimize OSPF as needed.
Verify SNMP traps are sent to SNMP collector.
All unicast and multicast traffic should re-converge with proportionate packet loss.
Verify traffic destined for CoPP classes is policed as expected.
Verify OSPF interface status for the affected links.
Verify OSPF neighbor changes and authentication.
Verify OSPF DB/Topology consistency.
Verify OSPF routes and forwarding table consistency..
Verify OSPF multi-path load-balancing.
Verify HW and SW entries are properly programmed and synchronized.
Verify PIM neighbor status.
Verify PIM both multipath and non-multipath functionalities.
Verify AutoRP mapping.
Verify static RP mapping as the backup of auto RP.
Verify MSDP neighbors and SA cache consistency.
Verify multicast HW and SW entries are properly programmed and synchronized.
On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.
Verify PIM source register and register stop.

pass

L3 Port-channel Failure/Recovery between Distribution to ToR N3k Layer 3 [Interop between N7K & N3K; C6K & N3K]

Verify BFD peer detection and client notifications.

Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.

pass

Verify the L2 forwarding table should remove entries of the affected link.

Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.

Verify SPAN is mirroring packets correctly.

Verify OTV traffic reconverges and optimize OSPF as needed.

Verify SNMP traps are sent to SNMP collector.

All unicast and multicast traffic should re-converge with proportionate packet loss.

Verify traffic destined for CoPP classes is policed as expected.

Verify OSPF interface status for the affected links.

Verify OSPF neighbor changes and authentication.

Verify OSPF DB/Topology consistency.

Verify OSPF routes and forwarding table consistency..

Verify OSPF multi-path load-balancing.

Verify HW and SW entries are properly programmed and synchronized.

Verify PIM neighbor status.

Verify PIM both multipath and non-multipath functionalities.

Verify AutoRP mapping.

Verify static RP mapping as the backup of auto RP.

Verify MSDP neighbors and SA cache consistency.

Verify multicast HW and SW entries are properly programmed and synchronized.

On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.

Verify PIM source register and register stop.

Verify BFD peer detection and client notifications.

Verify port-channel load balancing and rbh assignment

pass

L3 port-channel member failure/recovery

Verify traffic switches to high Bandwidth port-channels for both unicast and multicast when member failure and traffic will switch back when member recovers.

Verify LACP rebundle for port-channel after member recover.

	OTV VDC L3 Link Failure/Recovery	<p>The traffic should be able to re-converge within acceptable time.</p> <p>Verify the convergence pattern is as expected.</p> <p>Verify the route tables for both unicast and multicast are updated correctly.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p> <p>Verify traffic will recover after link recovery.</p>		
2.3. Clear OSPF Neighbors/Process/Routes	Clear OSPF Neighbors/Process/Routes	<p>All unicast and multicast traffic should re-converge.</p> <p>Verify OSPF IPv4/IPv6 neighbors will restart and come back correctly.</p> <p>Verify that the hardware entries are properly removed and re-installed during the neighbor/process flapping.</p> <p>Verify that CDP/LLDP does not lose peer information.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p> <p>Verify OSPF multi-path load-balancing.</p> <p>Verify HW and SW entries are properly programmed and synchronized.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized.</p> <p>Verify BFD peer detection and client notifications.</p> <p>Verify the route tables for both unicast and multicast are updated correctly.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p>		
2.4. Clear IPv4/IPv6 Multicast Routes	Clear IPv4/IPv6 Multicast Routes	<p>All multicast traffic should re-converge.</p> <p>Verify periodic PIM joins are received and sent upstream after clearing.</p> <p>Verify that the multicast hardware entries are properly removed and re-installed during the mroute flaps</p> <p>Verify that CDP/LLDP does not lose peer information.</p> <p>Verify that no flooding happens after traffic convergence.</p>	pass	

		<p>Verify PIM neighbor status.</p> <p>Verify PIM both multipath and non-multipath functionalities.</p> <p>Verify AutoRP mapping.</p> <p>On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.</p> <p>Verify PIM source register and register stop.</p> <p>Verify IGMP/MLD snooping entries are deleted and re-learned correctly after query from the IGMP snooping router.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p>		
2.5. Reload and Power Cycle Switch	Reload and Power Cycle Edge/Core Switch	<p>Verify BGP neighbor's status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify BGP multi-path load-balancing.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p> <p>Verify BGP reconvergence (control-plane & data-plane).</p> <p>Verify OSPF interface status for the affected links.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify OSPF multi-path load-balancing.</p> <p>Verify HW and SW entries are properly programmed and synchronized.</p> <p>Verify PIM neighbor status.</p> <p>Verify PIM both multipath and non-multipath functionalities.</p> <p>Verify AutoRP mapping and boundaries.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p>	pass	CSCul01126

Reload and Power Cycle Distribution Switch

Verify multicast HW and SW entries are properly programmed and synchronized.

Verify STP port states during and after reload.

Verify HSRP peers status during and after reload.

Verify CDP/LLDP status during reload on the peers and after reload on the peers and DUT.

Verify the L2 forwarding table should remove entries of the affected link at the neighbor switch.

Verify HSRP MAC in ARP table.

Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.

Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.

On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after reload.

Verify that no flooding happens after traffic convergence.

Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.

Verify IGMP/MLD snooping entries are deleted for the affected links at the access switches and re-learnt correctly on the alternative links after query from the IGMP snooping router.

Verify ACL/QoS TCAM is programmed correctly to share for ACL's and features that allow for sharing and verify ACL's are not sharing when not expected.

Verify SPAN is mirroring packets correctly.

Verify SNMP traps are sent to SNMP collector.

All unicast and multicast traffic should re-converge.

Verify traffic destined for CoPP classes is policed as expected.

Verify OSPF interface status for the affected links.

Verify OSPF neighbor changes and authentication.

Verify OSPF DB/Topology consistency.

Verify OSPF routes and forwarding table consistency..

Verify OSPF multi-path load-balancing.

Verify HW and SW entries are properly programmed and synchronized.

Verify PIM neighbor status.

Verify PIM both multipath and non-multipath functionalities.

Verify AutoRP mapping and boundaries.

Verify static RP mapping as the backup of auto RP.

Verify MSDP neighbors and SA cache consistency.

pass

	vPC peer switch VDC reload	<p>Verify multicast HW and SW entries are properly programmed and synchronized.</p> <p>On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.</p> <p>Verify PIM source register and register stop.</p> <p>Verify GRE Tunnel re-route due to transport disruption.</p> <p>Verify MTU fragmentation and reassembling at tunnel edge.</p> <p>Verify BFD peer detection and client notifications.</p> <p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC peer switch reload.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters)</p> <p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC peer switch reload.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters)</p>	pass	
2.6. Supervisor and Fabric HA	Supervisor HA on the edge/core layer	<p>Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.</p> <p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p> <p>Verify BGP reconvergence (control-plane & data-plane).</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after SSO.</p>	pass	

Supervisor HA on the Distribution layer

Verify BFD peer should not flap during and after SSO.
No traffic loss is expected.
Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.
Verify STP port states during and after SSO.
Verify HSRP peers status during and after SSO.
Verify CDP/LLDP status after SSO.
Verify ARP tables remain unaffected
Verify HSRP MAC in ARP table.
Verify OTV ARP optimization/ARP caching works as expected after SSO.
Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.
Verify automated mapping of OTV sites multicast groups to transport multicast group.
Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.
Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.
On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after SSO.
Verify IGMP snooping entries remain unaffected.
Verify that no flooding happens after traffic convergence.
Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.
Verify SPAN is mirroring packets correctly during and after SSO.
Verify SNMP traps are sent to SNMP collector.
Verify traffic destined for CoPP classes is policed as expected.
Verify OSPF interface status.
Verify OSPF neighbor changes and authentication.
Verify OSPF DB/Topology consistency.
Verify OSPF routes and forwarding table consistency..
Verify HW and SW entries are properly programmed and synchronized after SSO.
Verify PIM neighbor status.
Verify static RP mapping as the backup of auto RP.
Verify MSDP neighbors and SA cache consistency.

pass

	Fabric Failover on the Edge/Core and Distribution Layers	<p>Verify multicast HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify BFD peer should not flap during and after SSO.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters) before and after SSO</p> <p>No traffic loss is expected.</p> <p>Verify there is no impact to data plane and control plane on Fabric failover with no oversubscription</p>		
2.7. Line Card OIR and Reset	L3 port-channel member failure/recovery, on OIR/reset line card	<p>Verify hitless operation for non-affected ports</p> <p>Verify traffic load-balancing for distributed port-channels before and after OIR/reset</p> <p>Verify BGP/ IGP/ PIM reconvergence (control-plane & data plane)</p> <p>Verify BFD peer detection and client notifications</p> <p>Verify LACP interoperability for distributed port-channels</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected line card. Verify that CDP/LLDP peer is removed for disrupted line cards.</p> <p>Verify the L2 forwarding table should be re-learnt correctly after OIR/reset.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p>	pass	
	L2 port-channel member failure/recovery, on OIR/reset line card	<p>Verify port-channel load balancing and rbh assignment</p> <p>Verify LACP interoperability for distributed port-channels</p> <p>Verify STP port states after OIR/reset are in the expected forwarding mode.</p> <p>Verify HSRP peers status after OIR/reset.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify IGMP/MLD snooping entries are deleted for the links of affected line card and re-learnt correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>Verify the L2 forwarding table should be re-learnt correctly after OIR/reset.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p>	pass	

<p>vPC leg failure/recovery, on OIR/reset line card</p>	<p>Verify SPAN is mirroring packets correctly.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic. Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC leg is shut. Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>
<p>vPC leg member failure/recovery on OIR/reset line card</p>	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC leg member is shut (assuming there are 2 members on each vPC leg). Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	<p>pass</p>
<p>vPC peer-link failure/recovery on OIR/reset line card</p>	<p>Verify that the operational secondary vPC peer will bring down the vPC member ports.</p> <p>Verify that secondary peer will suspend the vpc vlan svi's.</p> <p>Verify that on recovery, the original states will be re-established.</p>	<p>pass</p>
<p>vPC Peer-keepalive failure/recovery on OIR/reset line card</p>	<p>There are no expected effects, both vPC peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>Verify that on recovery, the original states will be re-established.</p>	<p>pass</p>
<p>vPC peer-link and peer-keepalive failure on OIR/reset line card</p>	<p>If the keep-alive fails first followed by vPC peer link, then both vPC peers will become active. Verify dual-active scenario is encountered and with the peer-switch feature enabled, ensure the downstream device does not detect any spanning-tree misconfigurations.</p> <p>If the vPC peer-link fails first followed by the keep-alive link, the secondary should keep it's vPC member ports suspended.</p> <p>With vPC auto-recovery configured if the vPC peer-link fails first followed by the keep-alive link, the secondary will keep it's vPC member ports suspended for the duration of three consecutive keepalive failures. After the timer expires the member ports will be unsuspending and the system will change role to primary causing Dual-active scenario.</p>	<p>pass</p>
<p>vPC peer-link and peer-keepalive recovery on OIR/reset line card</p>	<p>If keep-alive is recovered first, the active/secondary switch is determined by the role priority and the secondary switch will suspend vPC member ports and vpc svi's.</p> <p>If vpc peer link is recovered first followed by keep alive, the active/secondary switch is determined by the role priority and the system resumes.</p>	<p>pass</p>

2.8. ISSU/ISSD	ISSU/ISSD	<p>Verify if ISSU image compatibility for non-disruptive upgrade/downgrade</p> <p>Verify ISSU/ISSD happens as expected. OSPF graceful restart, PIM triggered Joins should work as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after ISSU/ISSD.</p> <p>Verify STP port states during and after ISSU/ISSD.</p> <p>Verify HSRP peers status during and after ISSU/ISSD.</p> <p>Verify CDP/LLDP status after ISSU/ISSD.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the distribution switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after ISSU/ISSD.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after ISSU/ISSD.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p> <p>Verify BGP reconvergence for control-plane.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p> <p>Verify HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p>	Pass with exception	<p>CSCul30416</p> <p>CSCul36654</p> <p>CSCul48388</p> <p>CSCul81685</p> <p>CSCul88464</p> <p>CSCul98066</p>
----------------	-----------	--	---------------------	---

		<p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify BFD peer should not flap during and after ISSU/ISSD.</p> <p>No traffic loss is expected.</p> <p>If ISSU is disruptive, verify that all unicast/multicast traffic reconverges.</p>		
2.9. Configuration Change	<p>Perform VPC Vlan add and delete</p> <p>Perform VPC SVI add and delete</p> <p>Perform Non-VPC Vlan add and delete</p> <p>Perform Non-VPC SVI add and delete</p> <p>Remove VDC and add it back</p> <p>Enable/Disable IGMP snooping</p> <p>Perform HSRP active/standby switchover by changing priority</p>	<p>Verify STP port states after each change are in the expected forwarding mode.</p> <p>Verify HSRP peers status after each change.</p> <p>Verify the L2 forwarding table should be updated correctly after each change.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted and re-learned correctly upon each disruption.</p> <p>DHCP relay configured on the spine switches should remain unaffected after each change.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP after each change.</p> <p>All unicast and multicast traffic should re-converge with expected packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify that all unicast/multicast traffic convergence.</p>		
2.10.FabricPath – Network disruptions				
2.10.1. FabricPath – Link Failure/Recovery	FabricPath - Core Link Failure/Recovery	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify HSRP peers status does not change.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>	pass	

	<p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers. On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link and re-learned correctly on the alternative link after query from the IGMP snooping router. Verify that IGMP/MLD membership is not affected on the routers.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP. Verify that IPv6 global HSRP is functional.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast. All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p>	
Fabricpath - Core Link member failure/recovery	<p>Verify port-channel load balancing and RBH assignment.</p> <p>Verify IS-IS database, topology and route distribution for metric change.</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>Verify that IGMP snooping entries change based on multi-destination tree topology change.</p> <p>The maximum traffic disruption for unicast/multicast should be in sub-second range for both upstream and downstream traffic. Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	pass
Fabricpath - vPC+ leg failure/recovery	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic or no loss.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC+ leg is shut. Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	pass
Fabricpath - vPC+ leg member failure/recovery	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC+ leg member is shut (assuming there are 2 members on each vPC+ leg).</p>	pass

	<p>Fabricpath - vPC+ peer-link failure/recovery (spine/leaf)</p> <p>Fabricpath - vPC+ Peer-keepalive failure/recovery</p> <p>Fabricpath - vPC+ peer-link and Peer-keepalive failure/recovery</p>	<p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>Verify that the operational secondary vPC+ peer will bring down the vPC+ member ports.</p> <p>Verify that secondary peer will not suspend the vPC+ vlan SVI's if "<i>dual-active exclude vlans</i>" is configured</p> <p>Verify on recovery that the operational secondary vPC+ peer will bring up the vPC+ member ports after the configured "<i>delay restore</i>" timer</p> <p>There are no expected effects; both vPC+ peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>When the keep-alive fails first followed by vPC+ peer link, the peers should continue to see each other through fabricpath network. The effect should be same as just peer-link failure.</p> <p>The recovery should be same as the peer-link recovery.</p>	<p>pass</p> <p>pass</p> <p>pass</p>	
<p>2.10.2. FabricPath – Reload</p>	<p>FabricPath - Spine Node failure/recovery</p>	<p>Verify Fabricpath multi-destination trees reconverge after root change on node failure.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the distribution switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on the other spine routers</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the other spine routers.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify that the MAC table, FP ISIS route table, ARP table, IP routing table, IGMP membership table, IGMP</p>	<p>Pass with exception</p>	<p>CSCuj95402</p>

	FabricPath - Leaf Node failure/recovery	<p>snooping table, Multicast routing table return to original state on recovery</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on recovery</p> <p>Verify Fabricpath multi-destination trees reconverge after leaf node failure.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify HSRP peers status does not change when CE or leaf switches are reloaded.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the spine routers.</p> <p>Verify that the MAC table, FP ISIS route table, IGMP snooping table return to original state on recovery</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on recovery</p>	pass	
2.10.3. FabricPath – Supervisor and Fabric HA	FabricPath – Supervisor HA on the spine nodes	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.</p> <p>Verify STP port states during and after SSO.</p> <p>Verify HSRP peers status during and after SSO.</p> <p>Verify CDP/LLDP status after SSO.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after SSO.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after SSO.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF interface status.</p>	pass	

	FabricPath - Fabric Failover on spine nodes	<p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify BFD peer should not flap during and after SSO.</p> <p>Verify vPC+ peer status (role, peer link, keepalive link and consistency parameters) before and after SSO</p> <p>No traffic loss is expected.</p> <p>Verify there is no impact to data plane and control plane on Fabric failover with no oversubscription</p>	pass	
2.10.4. FabricPath – Line card OIR and Reset	FabricPath – Line card OIR and Reset on spine nodes	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify hitless operation for non-affected ports</p> <p>Verify traffic load-balancing for distributed port-channels before and after OIR/reset</p> <p>Verify BFD peer detection and client notifications</p> <p>Verify LACP interoperability for distributed port-channels</p> <p>Verify STP port states after OIR/reset are in the expected forwarding mode.</p> <p>Verify HSRP peers status after OIR/reset.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected line card. Verify that CDP/LLDP peer is removed for disrupted line cards.</p> <p>Verify the L2 forwarding table should be re-learnt correctly after OIR/reset.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the links of affected line card and re-learnt correctly on the alternative link after query from the IGMP snooping router.</p>	pass	

<p>FabricPath – FP core port-channel member failure/recovery, on OIR/reset line card</p>	<p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify port-channel load balancing and rbh assignment</p>	<p>pass</p>
<p>FabricPath – vPC+ leg failure/recovery on OIR/reset line card</p>	<p>Verify that IGMP/MLD membership is not affected.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>
<p>FabricPath – vPC+ leg member failure/recovery on OIR/reset line card</p>	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC+ leg is shut.</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>
<p>FabricPath – vPC+ peer-link failure/recovery on OIR/reset line card</p>	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC+ leg member is shut (assuming there are 2 members on each vPC+ leg).</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	<p>pass</p>
<p>FabricPath – vPC+ peer-link failure/recovery on OIR/reset line card</p>	<p>Verify that the operational secondary vPC+ peer will bring down the vPC+ member ports.</p> <p>Verify that secondary peer will not suspend the vPC+ vlan SVI's if "<i>dual-active exclude vlans</i>" is configured</p> <p>Verify on recovery that the operational secondary vPC+ peer will bring up the vPC+ member ports after the configured "<i>delay restore</i>" timer</p>	<p>pass</p>
<p>FabricPath – vPC+ Peer-keepalive failure/recovery on OIR/reset line card Fabricpath - vPC+ peer-link and Peer-keepalive failure/recovery on OIR/reset line card</p>	<p>There are no expected effects; both vPC+ peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>When the keep-alive fails first followed by vPC+ peer link, the peers should continue to see each other through fabricpath network. The effect should be same as just peer-link failure.</p> <p>The recovery should be same as the peer-link recovery.</p>	<p>pass</p>

<p>2.10.5. FabricPath – ISSU/ISSD</p>	<p>FabricPath – ISSU/ISSD</p>	<p>Verify if ISSU image compatibility for non-disruptive upgrade/downgrade</p> <p>Verify ISSU/ISSD happens as expected. OSPF graceful restart, PIM triggered Joins should work as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after ISSU/ISSD.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify STP port states during and after ISSU/ISSD.</p> <p>Verify HSRP peers status during and after ISSU/ISSD.</p> <p>Verify CDP/LLDP status after ISSU/ISSD.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after ISSU/ISSD.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after ISSU/ISSD.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p> <p>Verify HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p>	<p>pass</p>	
---------------------------------------	-------------------------------	---	-------------	--

	FabricPath – End Hosts Change	<p>Verify ARP and MAC tables change as expected.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches.</p> <p>DHCP relay configured on the spine switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Monitor all unicast/multicast traffic convergence.</p>		
2.10.7. FabricPath – Configuration Change	<p>Perform FP Vlan add and delete</p> <p>Perform FP SVI add and delete</p> <p>Perform Non-FP Vlan add and delete</p> <p>Perform Non-FP SVI add and delete</p> <p>Perform FP MT root move by changing priority</p> <p>Enable/Disable IGMP snooping</p>	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers after each change.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after each change.</p> <p>Verify that no flooding happens after traffic convergence after each change.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines after each change.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches after each change.</p> <p>DHCP relay configured on the spine switches should remain unaffected after each change.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP after each change.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast on all the affected FP switches.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Monitor all unicast/multicast traffic convergence.</p>	pass	

2.11.OTV – Network Disruptions				
2.11.1. OTV – Reload	OTV – Reload	<p>Verify HSRP isolation across OTV sites works as expected after reload/recovery.</p> <p>Verify OTV ARP optimization/ARP caching works as expected after reload/recovery.</p> <p>Verify unknown unicast traffic doesn't flood.</p> <p>Verify STP is blocked across OTV sites.</p> <p>Verify the Secondary Adj. Server will take over after primary Adj. Server failover.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.</p> <p>Verify automated mapping of OTV sites multicast groups to transport multicast group.</p> <p>Verify IGMP snooping entries are properly relearned on the affected OTV switches.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
2.11.2. OTV – Move/Add/Change Hosts	OTV – MAC move/Add/Change Hosts	<p>Verify HSRP isolation across OTV sites works as expected.</p> <p>Verify OTV ARP optimization/ARP caching works as expected.</p> <p>Verify unknown unicast traffic doesn't flood.</p> <p>Verify the new hosts's macs are learnt across OTV sites.</p> <p>Verify STP is blocked across OTV sites.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.</p> <p>Verify automated mapping of OTV sites multicast groups to transport multicast group.</p> <p>Verify IGMP snooping entries are properly relearned on the affected OTV switches.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
2.11.3. OTV – Configuration Change	<p>Add and delete OTV VLAN</p> <p>Add and delete OVT SVI</p> <p>Enable and disable proxy ARP</p> <p>Enable and disable suppression ARP</p>	<p>Verify HSRP isolation across OTV sites works as expected</p> <p>Verify OTV ARP optimization/ARP caching/ARP suppression works as expected.</p> <p>Verify unknown unicast traffic doesn't flood.</p> <p>Verify STP is blocked across OTV sites.</p>		

	<p>Enable and disable igmp snooping</p> <p>Add and delete overlay interface</p> <p>Dynamically changing Adj Server</p> <p>Add/remove/flush MAC entries</p> <p>Add/remove/flush ARP entries</p> <p>Add/remove/flush multicast group entries</p> <p>Add/remove/flush active multicast source entries</p>	<p>Verify new Adj. Server works as expected.</p> <p>Verify the new hosts's macs are learnt across OTV sites.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.</p> <p>Verify automated mapping of OTV sites multicast groups to transport multicast group.</p> <p>Verify IGMP snooping entries are properly relearned on the affected OTV switches.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
2.12.UCS – Disruptions				
2.12.1. UCS – Link Failure/Recovery	<p>UCS - Link Failure/Recovery Between FI and N7K: VPC</p> <p>FI Uplink port-channel member failure/recovery: 101-01 n7k vpc</p> <p>FI Uplink port-channel failure/recovery: 101-01 n7k vpc</p> <p>FI to IOM port-channel member failure/recovery: 101-01 n7k vpc</p>	<p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify VM does not lose network connectivity.</p> <p>Measure traffic convergence for each disruption</p> <p>Verify traffic recovery within the expected time frame.</p> <p>Verify that rehashing is performed according to the port-channel protocol (LACP) deployed.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify MAC learning on FI server links is not impacted.</p> <p>Verify traffic should switch to other FI and re-converge with expected packet loss.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify traffic recovery within the expected time frame.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact.</p>		

	<p>FI to IOM port-channel failure/recovery:</p> <p>FI cluster link member failure/recovery: 101-01 n7k vpc</p> <p>FI to FI isolation/recovery: 101-01 n7k vpc</p>	<p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links is not impacted.</p> <p>Verify traffic recovery within the expected time frame.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify traffic should have no impact.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links is not impacted.</p> <p>Verify traffic should re-converge after FI cluster link recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after FI cluster link recovery.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink after FI cluster link recovery.</p> <p>Verify mac learning on other FI server links after FI cluster link recovery.</p>		
<p>2.12.2. UCS – Fabric Interconnect Reload and Power Cycle</p>	<p>UCS – Fabric Interconnect Reload and Power Cycle: 101-01 n7k vpc</p>	<p>Verify traffic recovery within the expected time frame.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify that traffic flows accordingly through the uplink switches following the VPC model.</p> <p>Verify there is no mac address learning on other FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p>		

		<p>Verify VM does not lose network connectivity.</p> <p>Measure traffic convergence for each disruption</p>		
2.12.3. UCS – IOM OIR	UCS – IOM OIR	<p>Verify traffic recovery within the expected time frame.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify there is no mac address learning on other FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify VM does not lose network connectivity.</p>		
2.12.4. UCS – Blade OIR	UCS – Blade OIR	<p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after blade recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify mac learning on FI server links after blade recovery.</p> <p>Verify that no flooding happens after traffic convergence after blade recovery.</p> <p>Verify that IGMP snooping is working as expected after blade recovery.</p> <p>Verify when blade is re-inserted that hypervisor and VMs are restored.</p>		
	Perform live blade OIR (same slot, same chassis)	<p>Remove live blade and re-insert into the same slot within the same chassis.</p> <p>Verify when blade is re-inserted that hypervisor and vm are properly restored.</p>		

Perform live blade OIR (different slot, same chassis)

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Remove live blade and decommission from slot. Then re-insert the blade into a different slot within the same chassis, and associate the service profile to the blade.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Perform maintenance blade oir (different slot, different chassis)

Gracefully shutdown VMs and blade.

Dissociate service profile from blade.

Remove the blade and accept notifications.

Perform a blade swap (B200 with B22)
for a blade upgrade

In a B-Series chassis perform a blade
upgrade/downgrade (B22/B200)

Insert the blade into a different slot in a different chassis, and associate the service profile to the blade.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the same HDDs are retained throughout the process.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

	<p>In a B-Series chassis perform a complete blade upgrade/downgrade (B22/B200)</p>	<p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the same HDDs are retained throughout the process.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify FI uplink static pinning works as expected.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after blade recovery.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify when blade is re-inserted that hypervisor and vm are properly restored.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify FI uplink static pinning works as expected.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after blade recovery.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify that the HDD OIR in a RAID 1 Mirrored system does not impact the VMs.</p>		
<p>2.12.5. UCS – Chassis Reload and Power Cycle</p>	<p>UCS – Chassis Reload and Power Cycle</p>	<p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p>		

		<p>Verify traffic should re-converge after chassis IOM and blade recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after chassis IOM and blade recovery.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after chassis IOM and blade recovery.</p> <p>Verify that no flooding happens after traffic convergence after chassis IOM and blade recovery.</p> <p>Verify that IGMP snooping is working as expected after chassis IOM and blade recovery.</p> <p>Verify VM network connectivity is restored.</p>		
2.12.6. UCS – FI image and IOM Firmware Upgrade	UCS – FI image and IOM Firmware Upgrade	<p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify traffic should re-converge after IOM firmware upgraded.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after IOM firmware upgraded.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after IOM firmware upgraded.</p> <p>Verify that no flooding happens after traffic convergence after IOM firmware upgraded.</p> <p>Verify that IGMP snooping is working as expected after IOM firmware upgraded.</p> <p>Verify VM network connectivity is restored.</p>		
2.12.7. UCS – Blade adapter Firmware upgrade	UCS – Blade adapter Firmware upgrade	<p>Verify FI uplink static pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify traffic should re-converge after blade adapter firmware upgraded.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade adapter firmware upgraded.</p> <p>Verify proper MAC address learning on both fabric interconnects and Nexus 7000 switches.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after blade adapter firmware upgraded.</p> <p>Verify that no flooding happens after traffic convergence after blade adapter firmware upgraded.</p> <p>Verify that IGMP snooping is working as expected after blade adapter firmware upgraded.</p> <p>Verify VM network connectivity is restored.</p>		

	<p>Migrate live VM across different blades, same chassis, same FI pair (VMWare vDS)</p> <p>Migrate live VM across different blades, different chassis, same FI pair (VMWare vDS)</p> <p>Migrate live VM across different blades, different chassis, different FI pair (VMWare vDS)</p>	<p>Verify that no faults are raised on either UCSM or vCenter during the operation.</p> <p>Verify that the VM migration is properly executed while following the best practices and user guide.</p> <p>Verify that the VM's vNICs and port profiles are still associated and configured properly before and after the migration through monitoring the CLI.</p> <p>Verify that the MAC address of the migrated VM is learned on the destined Fabric Interconnect and the corresponding upstream switch throughout the migration.</p> <p>Verify that the VMs within the testbed remain pingable between one another during and after the migration.</p> <p>Verify that the VM's network interfaces remain pingable from our management network before and after the migration.</p> <p>Verify that the VM is still reachable through an SSH, or Telnet session.</p> <p>Verify that no faults are raised on either UCSM or vCenter during the operation.</p> <p>Verify that the VM migration is properly executed while following the best practices and user guide.</p> <p>Verify that the VM's vNICs and port profiles are still associated and configured properly before and after the migration through monitoring the CLI.</p> <p>Verify that the MAC address of the migrated VM is learned on the destined Fabric Interconnect and the corresponding upstream switch throughout the migration.</p> <p>Verify that the VMs within the testbed remain pingable between one another during and after the migration.</p> <p>Verify that the VM's network interfaces remain pingable from our management network before and after the migration.</p> <p>Verify that the VM is still reachable through an SSH, or Telnet session.</p> <p>Verify that no faults are raised on either UCSM or vCenter during the operation.</p> <p>Verify that the VM migration is properly executed while following the best practices and user guide.</p> <p>Verify that the VM's vNICs and port profiles are still associated and configured properly before and after the migration through monitoring the CLI.</p> <p>Verify that the MAC address of the migrated VM is learned on the destined Fabric Interconnect and the corresponding upstream switch throughout the migration.</p> <p>Verify that the VMs within the testbed remain pingable between one another during and after the migration.</p> <p>Verify that the VM's network interfaces remain pingable from our management network before and after the migration.</p> <p>Verify that the VM is still reachable through an SSH, or Telnet session.</p> <p>Verify that no faults are raised on either UCSM or vCenter during the operation.</p> <p>Verify that the VM migration is properly executed while following the best practices and user guide.</p>		
2.12.10. UCS – NIC Bonding	Configure Active / Standby nic bonding	<p>Modify ifcfg-eth8 configuration file</p> <p>Modify ifcfg-eth9 configuration file</p>		

Configure Adaptive Load Balancing nic bonding

Create ifcfg-bond0 configuration file
Create Modprobe.conf file for mode1 active/standby nics
Verify that the bonding is successful
Perform an ifdown on eth8 which is the active nic
Verify standby nic eth9 becomes active after failover.
Perform an ifup on eth8 and verify it becomes standby
Verify ping and ssh sessions are all active
Verify FI uplink static pinning works as expected.
Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.
Verify there is no mac address learning on FI uplink.

Modify ifcfg-eth8 configuration file
Modify ifcfg-eth9 configuration file
Create ifcfg-bond0 configuration file
Create Modprobe.conf file for mode6 (ALB) nics
Verify that the bonding is successful
Perform an ifdown on eth8
Verify traffic continues without loss as secondary nic continues to forward traffic.
Perform ifup on eth8 and verify traffic continues to load balance between links.
Verify FI uplink static pinning works as expected.
Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.
Verify there is no mac address learning on FI uplink.

Perform FI Failover from Fi-A to Fi-B

Verify ping and ssh sessions are all active
login to FI CLI and enter local-mgmt and preform reload on FI-A
verify that the FI recovers and there are no critical error messages
verify that the vifs failover to FI-B and traffic resumes
verify that the vifs resume on FI-A and traffic resumes
Verify ping and ssh sessions are all active
Verify FI uplink static pinning works as expected.

<p>Create a profile client in UCSM</p>	<p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>
<p>Associate a port profile to a VM</p>	<p>Verify vCenter executes the command properly and that UCSM is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>
<p>Remove associated port profile and profile client in UCSM</p>	<p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p>

<p>Unassociate port profile from a VM</p>	<p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify vCenter executes the command properly and that UCSM is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode. Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>
<p>Remove unassociated port profile and profile client in UCSM</p>	<p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode. Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode. Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>
<p>Modify port profile and LAN pin group in UCSM</p>	<p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters. Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p>

Remove associated distributed virtual switch in UCSM

Create duplicate associated distributed virtual switch from a different FI cluster in UCSM

Remove duplicate associated

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.
Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.
Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.
Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.
Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.
Fault monitoring verification on both UCSM and vCenter.
Verify the expected behavior is properly following the best practice and user guide.
Verify UCSM executes the command properly and that vCenter is reflecting the operation.
Verify syncing between UCSM GUI and vCenter GUI.
Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.
Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.
Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.
Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.
Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.
Fault monitoring verification on both UCSM and vCenter.
Verify the expected behavior is properly following the best practice and user guide.
Verify UCSM executes the command properly and that vCenter is reflecting the operation.
Verify syncing between UCSM GUI and vCenter GUI.
Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.
Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.
Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.
Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.
Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.
Fault monitoring verification on both UCSM and vCenter.
Verify the expected behavior is properly following the best practice and user guide.
Verify UCSM executes the command properly and that vCenter is reflecting the operation.

	<p>distributed virtual switch from different FI-pair in UCSM</p>	<p>Verify syncing between UCSM GUI and vCenter GUI.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>		
<p>2.12.13. UCS – Server Clustering Tests</p>	<p>Convert pod to cluster setting in vCenter 5.1</p> <p>Configure and associate a shared datastore for cluster High Availability in vCenter 5.1</p>	<p>Verify vSphere GUI executes the command properly and that it is reflecting the proper operation.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that vCenter 5.1 acknowledges the creation of the cluster and its components.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify vSphere GUI executes the command properly and that it is reflecting the proper operation.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that vCenter 5.1 acknowledges the creation of the cluster and its components.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p>		

	<p>Enable VM Monitoring within the High Availability cluster</p>	<p>Fault monitoring verification on vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify vSphere GUI executes the command properly and that it is reflecting the proper operation.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Verify that vCenter 5.1 acknowledges the creation of the cluster and its components.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for all necessary data plane traffic are properly mapped to the network adapters in VMDirectPath (High-Performance) mode.</p> <p>Verify through UCSM and vCenter that VM-FEX port profiles for management plane traffic are properly mapped to the network adapters in standard performance mode.</p> <p>Fault monitoring verification on vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p>		
2.12.14. UCS – Service Profile Testing	<p>From UCSM GUI perform server shutdown for a scheduled maintenance.</p> <p>From UCSM GUI perform boot server to recover after a schedule maintenance</p> <p>From UCSM GUI perform a blade reset to simulate a blade failure</p>	<p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.</p> <p>Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.</p> <p>Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.</p> <p>Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.</p> <p>Fault monitoring verification on both UCSM and vCenter.</p> <p>Verify the expected behavior is properly following the best practice and user guide.</p> <p>Verify UCSM executes the command properly and that vCenter is reflecting the operation.</p> <p>Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.</p>		

From UCSM GUI perform a server profile (SP) rename for management purposes

From UCSM GUI perform a server profile (SP) clone for management purposes

From UCSM GUI perform a server profile (SP) template creation for portability and usability purposes

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Fault monitoring verification on both UCSM and vCenter.

From UCSM GUI perform service profile (SP) dis-association for a blade maintenance

Verify the expected behavior is properly following the best practice and user guide.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

Verify when blade is re-inserted that hypervisor and vm are properly restored.

From UCSM GUI perform a bind to a template for the reprovisioning of a newly inserted blade

Verify UCSM executes the command properly and that vCenter is reflecting the operation.

Verify syncing between UCSM GUI, vCenter GUI and KVM consoles.

Using the CLI, verify that the vNICs, MAC, and IP addresses are properly associated on all of the VMs' network adapters.

Verify that the reachability of all the affected interfaces is properly restored after each disruption and the network convergence is achieved.

Verify that the reachability of all the interfaces of non-affected VMs is preserved throughout the entire process.

Verify FI uplink static pinning works as expected.

Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.

Verify there is no mac address learning on FI uplink.

Verify mac learning on FI server links after blade recovery.

Fault monitoring verification on both UCSM and vCenter.

Verify the expected behavior is properly following the best practice and user guide.

DC2 test results

		NVT 2.6	
Test Case	Pass/Fail Verification	Status	Bugs
DC2 Setup			
Common Configuration for all switches	Verify SSH works through the management network on a dedicated vrf Verify Tacacs+ (tacacs.interop.cisco.com) and primary/backup servers Verify NTP/PTP and Time Zone : ntp.interop.cisco.com Verify Syslog to syslog.interop.cisco.com Verify DNS domain : interop.cisco.com and server : 172.28.92.9-10 Verify DNS search list: interop.cisco.com, cisco.com Verify CMP port connections to the management network. Verify CDP neighbors Verify SNMP agent (read community): public + interop; (private community): private + cisco Verify SNMP traps to monitor network events Verify UDLD neighbors and UDLD aggressive mode Verify LACP for link aggregation Verify BFD peering for all possible clients with default protocol timers for the clients on all relevant interfaces. Verify SSO/NSF and GR Verify CoPP function Verify SPAN ensuring cross-module SPAN. Configure Authentication for: OSPF/OSPFv3, HSRP/HSRPv6, MSDP, Layer 2 ISIS (FabricPath, OTV) Verify DHCP IP helper and primary/backup server	pass	CSCuj95182
Setup interfaces from DC2-Core-N7k-1 to Public network [AS1-1,AS1-2]	BGP: Verify Ipv4 eBGP peering between DC2-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath. BGP: Verify Ipv6 eBGP peering between DC2-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath. PIM: Verify PIM peering. Redistribute: Verify routes are redistributed according to configured policies.	pass	

	<p>Acl: Verify ACL policies are properly programmed in hardware and are functioning as expected.</p> <p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p> <p>For each feature enable label sharing and ensure it is actually deployed by checking the number of used TCAM entries (identify all the features that share labels).</p>		
	<p>Verify bank chaining of the TCAM.</p>		
<p>Setup interfaces from DC2-Core-N7k-2 to Public network [AS1-1,AS1-2]</p>	<p>BGP: Verify IPv4/IPv6 eBGP peering between DC2-Core-n7k-2 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>BGP: Verify Ipv6 eBGP peering between DC2-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>PIM: Verify PIM peering.</p> <p>Redistribute: Verify routes are redistributed according to configured policies.</p> <p>Acl: Verify ACL policies are properly programmed in hardware and are functioning as expected.</p> <p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p> <p>For each feature enable label sharing and ensure it is actually deployed by checking the number of used TCAM entries (identify all the features that share labels).</p> <p>Verify bank chaining of the TCAM.</p>	<p>pass</p>	
<p>Setup interfaces from DC2-Core-ASR9k-3 to Public network [AS1-1,AS1-2]</p>	<p>BGP: Verify IPv4/IPv6 eBGP peering between DC2-Core-ASR9k-3 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>BGP: Verify Ipv6 eBGP peering between DC2-Core-n7k-1 and AS1-1,AS1-2. Verify eBGP multipath.</p> <p>PIM: Verify PIM peering.</p> <p>Redistribute: Verify routes are redistributed according to configured policies.</p> <p>Acl: Verify ACL policies are functioning as expected.</p> <p>QoS: Verify QoS marking and policing.</p> <p>NAT: Verify NAT translation is properly handled at uplink interfaces including the GRE tunnel EP.</p> <p>NDE: Verify Netflow enabled interfaces monitor and export flow entries to external flow collector.</p> <p>GRE: Ensure GRE tunnels are up and all configured protocol peerings are fully established.</p>		

Setup interfaces from DC2-Core-N7k-1 to Distribution blocks	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p>	pass	
Setup interfaces from DC2-Core-N7k-2 to Distribution blocks	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p>	pass	
Setup interfaces from DC2-Core-ASR9k-3 to Distribution blocks	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p>		
Setup interfaces from Distribution N7k to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>OTV: Verify OTV ISIS adjacencies are properly established and OTV routing table. Verify the primary AS is being used. On the primary AS, verify all edge devices show up in the unicast replication list using "show otv adjacency-server replication-list".</p>	pass	
Setup interfaces from Distribution N7k to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>OTV: Verify OTV ISIS adjacencies are properly established and OTV routing table. Verify the primary AS is being used. On the primary AS, verify all edge devices show up in the unicast replication list using "show otv adjacency-server replication-list".</p>	pass	
Setup interfaces from Distribution C6kE8 VSS to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p>	pass	
Setup interfaces from Distribution C6kE8 to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p>	pass	
Setup interfaces from Distribution C6kE7 VSS to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p>	pass	
Setup interfaces from Distribution C6kE7 to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p>	pass	

Setup interfaces from Distribution C4k to the core switches	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p>	pass	
Setup interfaces from Distribution N7k to the ToR	<p>vPC: Verify vPC peer-gateway, vPC peer-switch, vPC Object tracking, vPC auto recovery. Verify vPC peer status, vPC priority and consistency parameters. Check MAC/ARP/igmp snooping synchronization.</p> <p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP Ipv4/IPv6 peering between s5 and s6. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP: Verify BOOTP functionality.</p> <p>OTV: Verify OTV AS adjacencies state and verify VLAN load-balancing for each of the OTV edge devices. Verify remote MAC learning in the OTV MAC table.</p>	pass	
Setup interface from DC2-Dist-N7k-101 to ToR FEX vPC	Verify FEX association with configured port-channels and that the FEX devices are up.	pass	
Setup interface from DC2-Dist-N7k-101 to ToR Layer 2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-N7k-101 to ToR N5k vPC	<p>Verify vPC status and consistency parameters.</p> <p>Verify spanning tree status on all vlans.</p>	pass	
Setup interface from DC2-Dist-N7k-101 to ToR Fabric Interconnect vPC	Verify vPC status and consistency parameters		
Setup interfaces from Distribution N7k to the ToR	<p>FabricPath: Verify FabricPath route and mac-table are built as expected. Verify IS-IS database. Verify multi-destination trees for unknown unicast, broadcast and multicast with root configured on the spine switches. Verify fabricpath load-balance works as expected</p> <p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p>	pass	

	<p>HSRP: Verify HSRP Ipv4/IPv6 peering between s51 & s52; s53 & s54. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch with G flag. STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP: Verify BOOTP functionality.</p> <p>OTV: Verify OTV AS adjacencies state and verify VLAN load-balancing for each of the OTV edge devices. Verify remote MAC learning in the OTV MAC table.</p>		
Setup interface from distribution DC2-Dist-N7k-102 to ToR FEX	Verify FEX association with configured port-channels and that the FEX devices are up.	pass	
Setup interface from DC2-Dist-N7k-102 to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-N7k-102 to ToR N5k FabricPath	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify the unknown unicast, broadcast and multicast multi-destination trees are built as expected.</p> <p>Verify fabricpath load-balance works as expected</p> <p>Verify IS-IS database, topology and route distribution.</p>	pass	
Setup interface from DC2-Dist-N7k-102 to ToR Fabric interconnect vPC+	Verify vPC+ status and consistency parameters.	pass	
Setup interface from DC2-Dist-N7k-102 to ToR L2 Switch vPC+	Verify vPC+ status and consistency parameters.	pass	
Setup interface from DC2-Dist-N7k-102 to ToR N3k Layer 3	<p>Verify OSPF/OSPFv3 peering.</p> <p>Verify PIM peering.</p>		
Setup interfaces from Distribution DC2-Dist-C6kE8-103-VSS to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>VSS: Verify VSS active/standby roles and VSL/MEC status. Verify Fast-redirect optimization</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP configuration.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p>	pass	

	<p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
Setup interface from DC2-Dist-C6kE8-103-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-C6kE8-103-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
Setup interface from DC2-Dist-C6kE8-104 to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-C6k-006-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
Setup interface from DC2-Dist-C6kE8-104 to ToR N5k MEC	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-C6kE8-104 to ToR N3k Layer 3	<p>Verify OSPF/OSPFv3.</p> <p>Verify PIM peering.</p>	pass	
Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>VSS: Verify VSS active/standby roles and VSL/MEC status. Verify Fast-redirect optimization</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP configuration.</p>	pass	

	<p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
Setup interface from DC2-Dist-C6kE7-105-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-C6kE7-105-VSS to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
Setup interfaces from Distribution C6k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
Setup interface from DC2-Dist-C6kE8-008-VSS to ToR L2 Switch	Verify spanning tree status on all vlans.	pass	
Setup interface from DC2-Dist-C6kE7-106 to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
Setup interface from DC2-Dist-C6kE7-106 to ToR N5k MEC	Verify spanning tree status on all vlans.	pass	
Setup interfaces from Distribution C4k to the ToR	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>MSDP: Verify MSDP peering and SA-cache</p> <p>PIM Snooping: Verify PIM snooping.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p>	pass	

	<p>HSRP: Verify HSRP peering between s5 and s6.</p> <p>STP: Verify RSTP parameters and port status.</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
Setup interface from DC2-Dist-C4k-107 to ToR Fabric Interconnect	Verify spanning tree status on all vlans.		
Setup vPC interface from ToR Layer 2 Switch to DC2-Dist-N7k-101	<p>STP: Verify RSTP parameters and port status.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>VACL, PAACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
Setup interfaces from ToR Layer 2 Switch vPC+ to the DC2-Dist-N7k-102	<p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PAACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
Setup interface from ToR N3k Layer 3 to DC2-Dist-N7k-102	<p>OSPF: Verify OSPFv2/OSPFv3 peering.</p> <p>PIM: Verify PIM peering.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>	pass	
Setup interface from ToR N3k Layer 3 to DC2-Dist-C6kE8-104	OSPF: Verify OSPFv2/OSPFv3 peering.	pass	

	<p>PIM: Verify PIM peering.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>ARP & MAC : Verify ARP and MAC addresses are properly learnt across all the forwarding engines.</p> <p>ACL: Verify that all the policies are properly programmed in hardware.</p> <p>QoS: Verify QoS marking.</p> <p>DHCP Relay Agent: Verify DHCP relay functionality.</p> <p>BOOTP Relay Agent: Verify BOOTP relay functionality.</p>		
Setup interface from ToR N5k vPC Switch to DC2-Dist-N7k-101	<p>vPC: Verify vPC peer status and consistency parameters. Check MAC/ARP/igmp snooping synchronization.</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
Setup interfaces from ToR N5k FabricPath to the DC2-Dist-N7k-102	<p>FabricPath: Verify FabricPath route and mac-table are built as expected. Verify IS-IS database. Verify multi-destination trees for unknown unicast, broadcast and multicast. Verify fabricpath load-balance works as expected</p> <p>HSRP: Verify HSRP MAC address is programmed in the mac table</p> <p>IGMP/MLD Snooping: Verify IGMP/MLD Snooping</p> <p>STP: Verify RSTP parameters and port status.</p> <p>VACL, PACL: Verify that all the policies are properly programmed in hardware.</p>	pass	
Setup interface from FEX to End Host (traffic generator)	<p>Verify spanning tree status (edge) on all vlans for the host ports.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>	pass	
Setup interface from FEX to End Host vPC (traffic generator)	<p>Verify spanning tree status (edge) on all vlans for the host ports.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>	pass	
Setup interface from FEX to UCS Fabric Interconnect	<p>Verify spanning tree status (edge) on all vlans for the host ports.</p> <p>Verify mac table is populated correctly.</p>		

	Verify IGMP/MLD snooping.		
Setup interface from FEX to UCS Fabric Interconnect vPC	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
Setup interface from FEX to UCS Fabric Interconnect vPC+	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
Setup interface from ToR Layer 2 Switch to End Host (traffic generator)	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
Setup interface from ToR Layer 2 Switch to UCS Fabric Interconnect	Verify spanning tree status (edge) on all vlans for the host ports. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
Setup interface from ToR N3k Layer 3 Switch to End Host (traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
Setup interface from ToR N5k FEX to End Host vPC (traffic generator)	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.	pass	
Setup interface from ToR N5k vPC to UCS Fabric Interconnect vPC	Verify spanning tree status on all vlans. Verify mac table is populated correctly. Verify IGMP/MLD snooping.		
Setup interface from ToR N5k FP to UCS Fabric Interconnect vPC+	Verify spanning tree status on all vlans.		

	<p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>		
Setup interface from ToR N5k FP to End Host vPC+ (Traffic generator)	<p>Verify spanning tree status on all vlans.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>		
Setup interface from ToR N5k FP to End Host (Traffic generator)	<p>Verify spanning tree status on all vlans.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>		
Setup interface from ToR N5k FP to ToR L2 switch	<p>Verify spanning tree status on all vlans.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>	pass	
Setup interface from ToR N5k FP to ToR L2 switch vPC+	<p>Verify spanning tree status on all vlans.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>	pass	
Setup interface from N5k FP ToR FEX vPC+ to End Hosts (Traffic generator)	<p>Verify spanning tree status on all vlans.</p> <p>Verify mac table is populated correctly.</p> <p>Verify IGMP/MLD snooping.</p>		
Setup for UCS 62xx FI to FEX	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards FEX.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and pinning.</p>		
Setup for UCS 62xx FI to FEX	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards ToR FEX.</p>		

	<p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to Layer 2 Switch	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards layer 2 switch.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and pinning.</p>		
Setup for UCS 62xx FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to N7k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N7k VPC.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to N7k FabricPath VPC+	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N7k VPC+.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to Layer 2 Switch	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards the layer 2 switch.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		

Setup for UCS 62xx FI to N5k VPC+	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC+.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to C6kE8 Standalone	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to C6kE8 VSS	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to C6kE7 Standalone	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		

Setup for UCS 62xx FI to C6kE7 VSS	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C6k.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to N5k VPC	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards N5k VPC.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup for UCS 62xx FI to C4k	<p>Verify the two FI's are in a cluster.</p> <p>Verify FI end host mode configuration.</p> <p>Verify uplink port-channels towards C4k.</p> <p>Verify dynamic pinning on the FI uplinks.</p> <p>Verify IOM to FI connectivity and port-channel mode.</p>		
Setup hypervisor for server virtualization	<p>Verify the hypervisor software installation on the B2xx Mx blade.</p> <p>Verify server's IP address can be pinged.</p> <p>Verify the configured VM's are up and running.</p> <p>Verify the distributed virtual switch is functional.</p> <p>Verify successful installation of operating systems.</p> <p>Verify traffic can be generated by the servers.</p>		
Setup Nexus 1000V	<p>Verify that the Nexus 1000V is installed.</p> <p>Verify the network configurations for control, packet and management vlans.</p> <p>Verify the configured VEM's are up and running.</p> <p>Verify the distributed virtual switch is functional.</p>		

	<p>Verify successful installation of operating systems.</p> <p>Verify traffic can be generated by the servers.</p>		
Setup VM FEX	Verify that policies are applied to the VM servers.		
Network Disruptions Test Cases			
Common checks for all network disruptions	<p>Verify that MEM and CPU Usage for Supervisors and line cards are comparable to previous releases.</p> <p>Verify that all unicast/multicast traffic convergence is comparable to previous releases.</p> <p>Verify UCS end host mode on FI and VM-FEX functionality.</p> <p>Verify UCS unicast/multicast traffic convergence</p>		
L2 Port-channel Failure/Recovery between Distribution and ToR devices	<p>Verify STP port states after link disruption are in the expected forwarding mode. Verify that the STP root does not change.</p> <p>Verify HSRP peers status does not change. Verify HSRP MAC in ARP table. Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify the L2 forwarding table should remove entries of the affected link at the access switch and re-learnt correctly on the alternative link.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that the L2 forwarding entries on all switches for nodes connected to the access layer are associated with the corresponding STP forwarding ports.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learnt correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the routers.</p> <p>Verify ACL TCAM is programmed correctly to share for ACL's and features that allow for sharing and verify ACL's are not sharing when not expected.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify isolated vlans remain to have complete separation from other ports within the same PVLAN but not from the promiscuous ports using proxy-arp.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify that IPv6 global HSRP is functional.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p>	pass	

L2 port-channel member failure/recovery between Distribution and ToR devices	<p>Verify SNMP traps are sent to SNMP collector</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify port-channel load balancing and rbh assignment</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast will be proportionate to number of members failed</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	pass
vPC leg failure/recovery between Distribution and ToR devices	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC leg is shut.</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	pass
vPC leg member failure/recovery between Distribution and ToR devices	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC leg member is shut (assuming there are 2 members on each vPC leg).</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	pass
vPC peer-link failure/recovery between Distribution vPC peer switches	<p>Verify that the operational secondary vPC peer will bring down the vPC member ports.</p> <p>Verify that secondary peer will suspend the vpc vlan svi's.</p> <p>Verify that on recovery, the original states will be re-established.</p>	pass
vPC Peer-keepalive failure/recovery between Distribution vPC peer switches	<p>There is no expected effects, both vPC peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>Verify that on recovery, the original states will be re-established.</p>	pass
vPC peer-link and keep-alive failure between Distribution vPC peer switches	<p>If the keep-alive fails first followed by vPC peer link, then both vPC peers will become active. Verify dual-active scenario is encountered and with the peer-switch feature enabled, ensure the downstream device does not detect any spanning-tree misconfigurations.</p> <p>If the vPC peer-link fails first followed by the keep-alive link, the secondary should keep it's vPC member ports suspended.</p> <p>With vPC auto-recovery configured if the vPC peer-link fails first followed by the keep-alive link, the secondary will keep it's vPC member ports suspended for the duration of three consecutive keepalive failures. After the timer expires the</p>	pass

L3 Port-channel Failure/Recovery between
Distribution to ToR N3k Layer 3 [Interop between N7K
& N3K; C6K & N3k]

Verify OSPF multi-path load-balancing.
Verify HW and SW entries are properly programmed and synchronized.
Verify PIM neighbor status.
Verify PIM both multipath and non-multipath functionalities.
Verify AutoRP mapping.
Verify static RP mapping as the backup of auto RP.
Verify MSDP neighbors and SA cache consistency.
Verify multicast HW and SW entries are properly programmed and synchronized.
On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.
Verify PIM source register and register stop.
Verify BFD peer detection and client notifications.
Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.
Verify the L2 forwarding table should remove entries of the affected link.
Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.
Verify SPAN is mirroring packets correctly.
Verify OTV traffic reconverges and optimize OSPF as needed.
Verify SNMP traps are sent to SNMP collector.
All unicast and multicast traffic should re-converge with proportionate packet loss.
Verify traffic destined for CoPP classes is policed as expected.
Verify OSPF interface status for the affected links.
Verify OSPF neighbor changes and authentication.
Verify OSPF DB/Topology consistency.
Verify OSPF routes and forwarding table consistency..
Verify OSPF multi-path load-balancing.
Verify HW and SW entries are properly programmed and synchronized.
Verify PIM neighbor status.
Verify PIM both multipath and non-multipath functionalities.
Verify AutoRP mapping.

pass

<p>L3 port-channel member failure/recovery</p> <p>OTV VDC L3 Link Failure/Recovery</p>	<p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized.</p> <p>On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.</p> <p>Verify PIM source register and register stop.</p> <p>Verify BFD peer detection and client notifications.</p> <p>Verify port-channel load balancing and rbh assignment</p> <p>Verify traffic switches to high Bandwidth port-channels for both unicast and multicast when member failure and traffic will switch back when member recovers.</p> <p>Verify LACP rebundle for port-channel after member recover.</p> <p>The traffic should be able to re-converge within acceptable time.</p> <p>Verify the convergence pattern is as expected.</p> <p>Verify the route tables for both unicast and multicast are updated correctly.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p> <p>Verify traffic will recover after link recovery.</p>	<p>pass</p>	
<p>Clear OSPF Neighbors/Process/Routes</p>	<p>All unicast and multicast traffic should re-converge.</p> <p>Verify OSPF IPv4/IPv6 neighbors will restart and come back correctly.</p> <p>Verify that the hardware entries are properly removed and re-installed during the neighbor/process flapping.</p> <p>Verify that CDP/LLDP does not lose peer information.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p> <p>Verify OSPF multi-path load-balancing.</p> <p>Verify HW and SW entries are properly programmed and synchronized.</p>		

	<p>Verify multicast HW and SW entries are properly programmed and synchronized.</p> <p>Verify BFD peer detection and client notifications.</p> <p>Verify the route tables for both unicast and multicast are updated correctly.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p>		
Clear IPv4/IPv6 Multicast Routes	<p>All multicast traffic should re-converge.</p> <p>Verify periodic PIM joins are received and sent upstream after clearing.</p> <p>Verify that the multicast hardware entries are properly removed and re-installed during the mroute flaps</p> <p>Verify that CDP/LLDP does not lose peer information.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify PIM neighbor status.</p> <p>Verify PIM both multipath and non-multipath functionalities.</p> <p>Verify AutoRP mapping.</p> <p>On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.</p> <p>Verify PIM source register and register stop.</p> <p>Verify IGMP/MLD snooping entries are deleted and re-learnt correctly after query from the IGMP snooping router.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify the hardware entries, LC programming, fabric programming, outgoing interface, forwarding engine entries, for both unicast and multicast are updated correctly.</p>	pass	
Reload and Power Cycle Edge/Core Switch	<p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify BGP multi-path load-balancing.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p> <p>Verify BGP reconvergence (control-plane & data-plane).</p> <p>Verify OSPF interface status for the affected links.</p> <p>Verify OSPF neighbor changes and authentication.</p>	pass	

Reload and Power Cycle Distribution Switch

Verify OSPF DB/Topology consistency.

Verify OSPF routes and forwarding table consistency..

Verify OSPF multi-path load-balancing.

Verify HW and SW entries are properly programmed and synchronized.

Verify PIM neighbor status.

Verify PIM both multipath and non-multipath functionalities.

Verify AutoRP mapping and boundaries.

Verify static RP mapping as the backup of auto RP.

Verify MSDP neighbors and SA cache consistency.

Verify multicast HW and SW entries are properly programmed and synchronized.

Verify STP port states during and after reload.

Verify HSRP peers status during and after reload.

Verify CDP/LLDP status during reload on the peers and after reload on the peers and DUT.

Verify the L2 forwarding table should remove entries of the affected link at the neighbor switch.

Verify HSRP MAC in ARP table.

Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.

Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.

On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after reload.

Verify that no flooding happens after traffic convergence.

Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.

Verify IGMP/MLD snooping entries are deleted for the affected links at the access switches and re-learnt correctly on the alternative links after query from the IGMP snooping router.

Verify ACL/QoS TCAM is programmed correctly to share for ACL's and features that allow for sharing and verify ACL's are not sharing when not expected.

Verify SPAN is mirroring packets correctly.

Verify SNMP traps are sent to SNMP collector.

All unicast and multicast traffic should re-converge.

Verify traffic destined for CoPP classes is policed as expected.

Verify OSPF interface status for the affected links.

Verify OSPF neighbor changes and authentication.

pass

<p>vPC peer switch VDC reload</p>	<p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify OSPF multi-path load-balancing.</p> <p>Verify HW and SW entries are properly programmed and synchronized.</p> <p>Verify PIM neighbor status.</p> <p>Verify PIM both multipath and non-multipath functionalities.</p> <p>Verify AutoRP mapping and boundaries.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized.</p> <p>On the multicast LHR, verify (*,G) and (S,G) creation based on SPT-threshold settings.</p> <p>Verify PIM source register and register stop.</p> <p>Verify GRE Tunnel re-route due to transport disruption.</p> <p>Verify MTU fragmentation and reassembling at tunnel edge.</p> <p>Verify BFD peer detection and client notifications.</p> <p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC peer switch reload.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters)</p> <p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC peer switch reload.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters)</p>	<p>pass</p>	
<p>Supervisor HA on the edge/core layer</p>	<p>Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.</p> <p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p> <p>Verify BGP reconvergence (control-plane & data-plane).</p>	<p>pass</p>	

Supervisor HA on the Distribution layer

Verify OSPF interface status.

Verify OSPF neighbor changes and authentication.

Verify OSPF DB/Topology consistency.

Verify OSPF routes and forwarding table consistency..

Verify HW and SW entries are properly programmed and synchronized after SSO.

Verify PIM neighbor status.

Verify static RP mapping as the backup of auto RP.

Verify MSDP neighbors and SA cache consistency.

Verify multicast HW and SW entries are properly programmed and synchronized after SSO.

Verify BFD peer should not flap during and after SSO.

No traffic loss is expected.

Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.

Verify STP port states during and after SSO.

Verify HSRP peers status during and after SSO.

Verify CDP/LLDP status after SSO.

Verify ARP tables remain unaffected

Verify HSRP MAC in ARP table.

Verify OTV ARP optimization/ARP caching works as expected after SSO.

Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.

Verify automated mapping of OTV sites multicast groups to transport multicast group.

Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.

Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.

On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after SSO.

Verify IGMP snooping entries remain unaffected.

Verify that no flooding happens after traffic convergence.

Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.

Verify SPAN is mirroring packets correctly during and after SSO.

Verify SNMP traps are sent to SNMP collector.

Pass with exception

CSCuI28020

<p>Fabric Failover on the Edge/Core and Distribution Layers</p>	<p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify BFD peer should not flap during and after SSO.</p> <p>Verify vPC peer status (role, peer link, keepalive link and consistency parameters) before and after SSO</p> <p>No traffic loss is expected.</p> <p>Verify there is no impact to data plane and control plane on Fabric failover with no oversubscription</p>	<p>pass</p>	
<p>L3 port-channel member failure/recovery, on OIR/reset line card</p>	<p>Verify hitless operation for non-affected ports</p> <p>Verify traffic load-balancing for distributed port-channels before and after OIR/reset</p> <p>Verify BGP/ IGP/ PIM reconvergence (control-plane & data plane)</p> <p>Verify BFD peer detection and client notifications</p> <p>Verify LACP interoperability for distributed port-channels</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected line card. Verify that CDP/LLDP peer is removed for disrupted line cards.</p> <p>Verify the L2 forwarding table should be re-learnt correctly after OIR/reset.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p>	<p>pass</p>	
<p>L2 port-channel member failure/recovery, on OIR/reset line card</p>	<p>Verify port-channel load balancing and rbh assignment</p>	<p>pass</p>	

	<p>Verify LACP interoperability for distributed port-channels</p> <p>Verify STP port states after OIR/reset are in the expected forwarding mode.</p> <p>Verify HSRP peers status after OIR/reset.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify IGMP/MLD snooping entries are deleted for the links of affected line card and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>Verify the L2 forwarding table should be re-learned correctly after OIR/reset.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>		
vPC leg failure/recovery, on OIR/reset line card	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC leg is shut.</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	pass	
vPC leg member failure/recovery on OIR/reset line card	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC leg member is shut (assuming there are 2 members on each vPC leg).</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	pass	
vPC peer-link failure/recovery on OIR/reset line card	<p>Verify that the operational secondary vPC peer will bring down the vPC member ports.</p> <p>Verify that secondary peer will suspend the vpc vlan svi's.</p> <p>Verify that on recovery, the original states will be re-established.</p>	pass	
vPC Peer-keepalive failure/recovery on OIR/reset line card	<p>There are no expected effects, both vPC peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p>	pass	

<p>vPC peer-link and peer-keepalive failure on OIR/reset line card</p>	<p>Verify that on recovery, the original states will be re-established.</p> <p>If the keep-alive fails first followed by vPC peer link, then both vPC peers will become active. Verify dual-active scenario is encountered and with the peer-switch feature enabled, ensure the downstream device does not detect any spanning-tree misconfigurations.</p> <p>If the vPC peer-link fails first followed by the keep-alive link, the secondary should keep it's vPC member ports suspended.</p>	<p>pass</p>	
<p>vPC peer-link and peer-keepalive recovery on OIR/reset line card</p>	<p>With vPC auto-recovery configured if the vPC peer-link fails first followed by the keep-alive link, the secondary will keep it's vPC member ports suspended for the duration of three consecutive keepalive failures. After the timer expires the member ports will be unsuspended and the system will change role to primary causing Dual-active scenario.</p> <p>If keep-alive is recovered first, the active/secondary switch is determined by the role priority and the secondary switch will suspend vPC member ports and vpc svi's.</p> <p>If vpc peer link is recovered first followed by keep alive, the active/secondary switch is determined by the role priority and the system resumes.</p>	<p>pass</p>	
<p>ISSU/ISSD</p>	<p>Verify if ISSU image compatibility for non-disruptive upgrade/downgrade</p> <p>Verify ISSU/ISSD happens as expected. OSPF graceful restart, PIM triggered Joins should work as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after ISSU/ISSD.</p> <p>Verify STP port states during and after ISSU/ISSD.</p> <p>Verify HSRP peers status during and after ISSU/ISSD.</p> <p>Verify CDP/LLDP status after ISSU/ISSD.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the distribution switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after ISSU/ISSD.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after ISSU/ISSD.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify BGP neighbors status and authentication.</p> <p>Verify BGP table and routing table consistency in accordance to the NEXT-HOP attribute settings.</p> <p>Verify proper BGP policy routing and filtering based on prefix, AS-PATH, LOCAL_PREFERENCE attributes.</p> <p>Verify the conditional injection of the default route from BGP into the IGP.</p> <p>Verify BGP recursive lookup scenario.</p>	<p>pass</p>	<p>CSCuI06388</p>

	<p>Verify BGP reconvergence for control-plane.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p> <p>Verify HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify BFD peer should not flap during and after ISSU/ISSD.</p> <p>No traffic loss is expected.</p> <p>If ISSU is disruptive, verify that all unicast/multicast traffic reconverges.</p>		
<p>Perform VPC Vlan add and delete</p> <p>Perform VPC SVI add and delete</p> <p>Perform Non-VPC Vlan add and delete</p> <p>Perform Non-VPC SVI add and delete</p> <p>Remove VDC and add it back</p> <p>Enable/Disable IGMP snooping</p> <p>Perform HSRP active/standby switchover by changing priority</p>	<p>Verify STP port states after each change are in the expected forwarding mode.</p> <p>Verify HSRP peers status after each change.</p> <p>Verify the L2 forwarding table should be updated correctly after each change.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted and re-learnt correctly upon each disruption.</p> <p>DHCP relay configured on the spine switches should remain unaffected after each change.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP after each change.</p> <p>All unicast and multicast traffic should re-converge with expected packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify that all unicast/multicast traffic convergence.</p>		
<p>FabricPath - Core Link Failure/Recovery</p>	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p>	<p>pass</p>	

<p>Fabricpath - Core Link member failure/recovery</p>	<p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify HSRP peers status does not change.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the routers.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify that IPv6 global HSRP is functional.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify port-channel load balancing and RBH assignment.</p> <p>Verify IS-IS database, topology and route distribution for metric change.</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>Verify that IGMP snooping entries change based on multi-destination tree topology change.</p> <p>The maximum traffic disruption for unicast/multicast should be in sub-second range for both upstream and downstream traffic.</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>	
---	---	-------------	--

<p>Fabricpath - vPC+ leg failure/recovery</p>	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic or no loss.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC+ leg is shut. Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>	
<p>Fabricpath - vPC+ leg member failure/recovery</p>	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC+ leg member is shut (assuming there are 2 members on each vPC+ leg). Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	<p>pass</p>	
<p>Fabricpath - vPC+ peer-link failure/recovery (spine/leaf)</p>	<p>Verify that the operational secondary vPC+ peer will bring down the vPC+ member ports.</p> <p>Verify that secondary peer will not suspend the vPC+ vlan SVI's if "<i>dual-active exclude vlans</i>" is configured</p> <p>Verify on recovery that the operational secondary vPC+ peer will bring up the vPC+ member ports after the configured "<i>delay restore</i>" timer</p>	<p>pass</p>	
<p>Fabricpath - vPC+ Peer-keepalive failure/recovery</p>	<p>There are no expected effects; both vPC+ peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p>	<p>pass</p>	
<p>Fabricpath - vPC+ peer-link and Peer-keepalive failure/recovery</p>	<p>When the keep-alive fails first followed by vPC+ peer link, the peers should continue to see each other through fabricpath network. The effect should be same as just peer-link failure. The recovery should be same as the peer-link recovery.</p>	<p>pass</p>	
<p>FabricPath - Spine Node failure/recovery</p>	<p>Verify Fabricpath multi-destination trees reconverge after root change on node failure.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the distribution switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on the other spine routers</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learned correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the other spine routers.</p>	<p>pass</p>	

<p>FabricPath - Leaf Node failure/recovery</p>	<p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>DHCP relay configured on the aggregation switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify that the MAC table, FP ISIS route table, ARP table, IP routing table, IGMP membership table, IGMP snooping table, Multicast routing table return to original state on recovery</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on recovery</p> <p>Verify Fabricpath multi-destination trees reconverge after leaf node failure.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify HSRP peers status does not change when CE or leaf switches are reloaded.</p> <p>Verify IGMP/MLD snooping entries are deleted for the affected link at the access switch and re-learnt correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify that IGMP/MLD membership is not affected on the spine routers.</p> <p>Verify that the MAC table, FP ISIS route table, IGMP snooping table return to original state on recovery</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines on recovery</p>	<p>pass</p>	
<p>FabricPath – Supervisor HA on the spine nodes</p>	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after SSO.</p> <p>Verify STP port states during and after SSO.</p> <p>Verify HSRP peers status during and after SSO.</p> <p>Verify CDP/LLDP status after SSO.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after SSO.</p>	<p>pass</p>	

<p>FabricPath - Fabric Failover on spine nodes</p>	<p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after SSO.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency..</p> <p>Verify HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after SSO.</p> <p>Verify BFD peer should not flap during and after SSO.</p> <p>Verify vPC+ peer status (role, peer link, keepalive link and consistency parameters) before and after SSO</p> <p>No traffic loss is expected.</p> <p>Verify there is no impact to data plane and control plane on Fabric failover with no oversubscription</p>	<p>pass</p>	
<p>FabricPath – Line card OIR and Reset on spine nodes</p>	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify hitless operation for non-affected ports</p> <p>Verify traffic load-balancing for distributed port-channels before and after OIR/reset</p> <p>Verify BFD peer detection and client notifications</p> <p>Verify LACP interoperability for distributed port-channels</p> <p>Verify STP port states after OIR/reset are in the expected forwarding mode.</p> <p>Verify HSRP peers status after OIR/reset.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected line card. Verify that CDP/LLDP peer is removed for</p>	<p>pass</p>	

	<p>disrupted line cards.</p> <p>Verify the L2 forwarding table should be re-learnt correctly after OIR/reset.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are deleted for the links of affected line card and re-learnt correctly on the alternative link after query from the IGMP snooping router.</p> <p>Verify SPAN is mirroring packets correctly.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p>		
<p>FabricPath – FP core port-channel member failure/recovery, on OIR/reset line card</p>	<p>Verify port-channel load balancing and rbh assignment</p> <p>Verify that IGMP/MLD membership is not affected.</p> <p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>Multicast DR should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>	
<p>FabricPath – vPC+ leg failure/recovery on OIR/reset line card</p>	<p>The maximum traffic disruption for unicast will be half for both upstream and downstream traffic.</p> <p>The maximum traffic loss for multicast upstream will be half and for downstream will be either 100% disrupted or no loss depending on which vPC+ leg is shut.</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p>	<p>pass</p>	
<p>FabricPath – vPC+ leg member failure/recovery on OIR/reset line card</p>	<p>The maximum traffic disruption for unicast should be in sub-second range for both upstream and downstream traffic.</p> <p>The maximum traffic loss for member failure multicast upstream will drop proportionate and for downstream will be either 50% disrupted or no loss depending on which vPC+ leg member is shut (assuming there are 2 members on each vPC+ leg).</p> <p>Multicast forwarder should not change.</p> <p>Verify that there is no protocol flapping.</p> <p>Verify port-channel load balancing and rbh assignment.</p> <p>Verify that IGMP/MLD membership is not affected.</p>	<p>pass</p>	
<p>FabricPath – vPC+ peer-link failure/recovery on OIR/reset line card</p>	<p>Verify that the operational secondary vPC+ peer will bring down the vPC+ member ports.</p> <p>Verify that secondary peer will not suspend the vPC+ vlan SVI's if "<i>dual-active exclude vlans</i>" is configured</p>	<p>pass</p>	

<p>FabricPath – vPC+ Peer-keepalive failure/recovery on OIR/reset line card</p> <p>Fabricpath - vPC+ peer-link and Peer-keepalive failure/recovery on OIR/reset line card</p>	<p>Verify on recovery that the operational secondary vPC+ peer will bring up the vPC+ member ports after the configured "delay restore" timer</p> <p>There are no expected effects; both vPC+ peers continue to synchronize MAC address tables, IGMP entries, no traffic disruptions.</p> <p>When the keep-alive fails first followed by vPC+ peer link, the peers should continue to see each other through fabricpath network. The effect should be same as just peer-link failure.</p> <p>The recovery should be same as the peer-link recovery.</p>	pass	
<p>FabricPath – ISSU/ISSD</p>	<p>Verify if ISSU image compatibility for non-disruptive upgrade/downgrade</p> <p>Verify ISSU/ISSD happens as expected. OSPF graceful restart, PIM triggered Joins should work as expected.</p> <p>Compare startup/running configuration on Active Sup and Standby Sup before and after ISSU/ISSD.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify STP port states during and after ISSU/ISSD.</p> <p>Verify HSRP peers status during and after ISSU/ISSD.</p> <p>Verify CDP/LLDP status after ISSU/ISSD.</p> <p>Verify HSRP MAC in ARP table.</p> <p>Verify HSRP MAC address is programmed as a router/static MAC on the active switch and a dynamic entry on the standby switch.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>On the aggregation switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after ISSU/ISSD.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify SPAN is mirroring packets correctly during and after ISSU/ISSD.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>All unicast and multicast traffic should re-converge.</p> <p>Verify traffic destined for CoPP classes is policed as expected.</p> <p>Verify OSPF interface status.</p> <p>Verify OSPF neighbor changes and authentication.</p> <p>Verify OSPF DB/Topology consistency.</p> <p>Verify OSPF routes and forwarding table consistency.</p>	pass	CSCul66808

	<p>Verify HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify PIM neighbor status.</p> <p>Verify static RP mapping as the backup of auto RP.</p> <p>Verify MSDP neighbors and SA cache consistency.</p> <p>Verify multicast HW and SW entries are properly programmed and synchronized after ISSU/ISSD.</p> <p>Verify BFD peer should not flap during and after ISSU/ISSD.</p> <p>No traffic loss is expected.</p> <p>If ISSU is disruptive, verify that all unicast/multicast traffic reconverges.</p>		
<p>FabricPath – MAC move</p>	<p>Verify ARP tables remain unaffected, MAC table shows mac move.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches.</p> <p>DHCP relay configured on the spine switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
<p>FabricPath – End Hosts Add</p>	<p>Verify ARP and MAC tables add the new hosts.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p>		

FabricPath – End Hosts Change	<p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches.</p> <p>DHCP relay configured on the spine switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify ARP and MAC tables change as expected.</p> <p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches.</p> <p>DHCP relay configured on the spine switches should remain unaffected.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Monitor all unicast/multicast traffic convergence.</p>		
<p>Perform FP Vlan add and delete</p> <p>Perform FP SVI add and delete</p> <p>Perform Non-FP Vlan add and delete</p> <p>Perform Non-FP SVI add and delete</p> <p>Perform FP MT root move by changing priority</p> <p>Enable/Disable IGMP snooping</p>	<p>Verify FabricPath route and mac-table are built as expected.</p> <p>Verify IS-IS database, topology and route distribution.</p> <p>Verify multi-destination trees for unknown unicast, broadcast and multicast.</p> <p>Verify fabricpath load-balance works as expected.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers after each change.</p> <p>On the spine switches, verify that the ARP are programmed as adjacencies for L3 next hop forwarding after each change.</p> <p>Verify that no flooding happens after traffic convergence after each change.</p> <p>Verify the L2/L3 forwarding entries are synchronized among the hardware forwarding engines after each change.</p> <p>Verify IGMP/MLD snooping entries are properly relearned on the affected FP switches after each change.</p> <p>DHCP relay configured on the spine switches should remain unaffected after each change.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP after each change.</p> <p>Verify that packets only traverse the fabric for known unicast/multicast destinations and flood through the fabric for unknown unicast, multicast when IGMP snooping is disabled, and broadcast on all the affected FP switches.</p>	pass	

	<p>All unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify SNMP traps are sent to SNMP collector.</p> <p>Monitor all unicast/multicast traffic convergence.</p>		
OTV – Reload	<p>Verify HSRP isolation across OTV sites works as expected after reload/recovery.</p> <p>Verify OTV ARP optimization/ARP caching works as expected after reload/recovery.</p> <p>Verify unknown unicast traffic doesn't flood.</p> <p>Verify STP is blocked across OTV sites.</p> <p>Verify the Secondary Adj. Server will take over after primary Adj. Server failover.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.</p> <p>Verify automated mapping of OTV sites multicast groups to transport multicast group.</p> <p>Verify IGMP snooping entries are properly relearned on the affected OTV switches.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
OTV – MAC move/Add/Change Hosts	<p>Verify HSRP isolation across OTV sites works as expected.</p> <p>Verify OTV ARP optimization/ARP caching works as expected.</p> <p>Verify unknown unicast traffic doesn't flood.</p> <p>Verify the new hosts's macs are learnt across OTV sites.</p> <p>Verify STP is blocked across OTV sites.</p> <p>Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.</p> <p>Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.</p> <p>Verify automated mapping of OTV sites multicast groups to transport multicast group.</p> <p>Verify IGMP snooping entries are properly relearned on the affected OTV switches.</p> <p>Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy arp and IGMP.</p> <p>Verify SNMP traps are sent to SNMP collector.</p>		
Add and delete OTV VLAN	<p>Verify HSRP isolation across OTV sites works as expected</p>		

Add and delete OVT SVI	Verify OTV ARP optimization/ARP caching/ARP suppression works as expected.		
Enable and disable proxy ARP	Verify unknown unicast traffic doesn't flood.		
Enable and disable suppression ARP	Verify STP is blocked across OTV sites.		
Enable and disable igmp snooping	Verify new Adj. Server works as expected.		
Add and delete overlay interface	Verify the new hosts's macs are learnt across OTV sites.		
Dynamically changing Adj Server	Verify that MAC's for SVI's are programmed as router/static entries on the switches where they are configured and learned as dynamic entries on the L2 peers.		
Add/remove/flush MAC entries	Verify head-end replication for multicast traffic on unicast-only transport works as expected, check the data-group mapping table for receiver information.		
Add/remove/flush ARP entries	Verify automated mapping of OTV sites multicast groups to transport multicast group.		
Add/remove/flush multicast group entries	Verify IGMP snooping entries are properly relearned on the affected OTV switches.		
Add/remove/flush active multicast source entries	Verify that secondary addresses provide the same capability and services to nodes through DHCP relay, HSRP services, ARP, proxy ARP and IGMP. Verify SNMP traps are sent to SNMP collector.		
UCS - Link Failure/Recovery	Verify FI uplink dynamic pinning works as expected. Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link. Verify SNMP traps are sent from FI to SNMP collector. Verify DHCP/BOOTP functionalities.		
FI Uplink port-channel member failure/recovery:	Verify unicast and multicast traffic should re-converge with minimal packet loss. Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact. Verify there is no mac address learning on FI uplink. Verify mac learning on FI server links is not impact. Verify that no flooding happens after traffic convergence. Verify that IGMP snooping is not affected.		
FI Uplink port-channel failure/recovery:	Verify unicast and multicast traffic should switch to other FI and re-converge with expected packet loss. Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected. Verify GARP is sent by other FI after fabric switchover. Verify there is no mac address learning on FI uplink.		

<p>FI to IOM port-channel member failure/recovery:</p>	<p>Verify mac learning on other FI server links.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify that IGMP snooping is working as expected.</p> <p>Verify unicast and multicast traffic should re-converge with minimal packet loss.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links is not impact.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify that IGMP snooping is not affected.</p> <p>FI to IOM port-channel failure/recovery:</p> <p>Verify unicast and multicast traffic should switch to other FI and re-converge with expected packet loss.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify that IGMP snooping is working as expected.</p>	
<p>FI cluster link failure/recovery:</p>	<p>Verify unicast and multicast traffic should have no impact.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works with no impact.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links is not impact.</p> <p>Verify that IGMP snooping is not affected.</p>	
<p>FI to FI isolation/recovery:</p>	<p>Verify unicast and multicast traffic should re-converge after FI cluster link recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after FI cluster link recovery.</p> <p>Verify there is no mac address learning on FI uplink after FI cluster link recovery.</p> <p>Verify mac learning on other FI server links after FI cluster link recovery.</p>	

<p>MEM and CPU:</p> <p>Convergence:</p>	<p>Verify that no flooding happens after traffic convergence after FI cluster link recovery.</p> <p>Verify that IGMP snooping is working as expected after FI cluster link recovery.</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – Fabric Interconnect Reload and Power Cycle</p> <p>MEM and CPU:</p> <p>Convergence:</p>	<p>Verify unicast and multicast traffic should switch to other FI and re-converge with expected packet loss.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify there is no mac address learning on other FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify that IGMP snooping is working as expected.</p> <p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – IOM OIR</p>	<p>Verify unicast and multicast traffic should switch to other FI and re-converge with expected packet loss.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected.</p> <p>Verify GARP is sent by other FI after fabric switchover.</p> <p>Verify there is no mac address learning on other FI uplink.</p> <p>Verify mac learning on other FI server links.</p> <p>Verify that no flooding happens after traffic convergence.</p> <p>Verify that IGMP snooping is working as expected.</p>		

	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – Blade OIR</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after blade recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade recovery.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after blade recovery.</p> <p>Verify that no flooding happens after traffic convergence after blade recovery.</p> <p>Verify that IGMP snooping is working as expected after blade recovery.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – Chassis Reload and Power Cycle</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after chassis IOM and blade recovery.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after chassis IOM and blade recovery.</p> <p>Verify there is no mac address learning on FI uplink.</p>		

	<p>Verify mac learning on FI server links after chassis IOM and blade recovery.</p> <p>Verify that no flooding happens after traffic convergence after chassis IOM and blade recovery.</p> <p>Verify that IGMP snooping is working as expected after chassis IOM and blade recovery.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – FI image and IOM Firmware Upgrade</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after IOM firmware upgraded.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after IOM firmware upgraded.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after IOM firmware upgraded.</p> <p>Verify that no flooding happens after traffic convergence after IOM firmware upgraded.</p> <p>Verify that IGMP snooping is working as expected after IOM firmware upgraded.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption</p>		
<p>UCS – Blade adapter Firmware upgrade</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after blade adapter firmware upgraded.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade adapter firmware upgraded.</p> <p>Verify there is no mac address learning on FI uplink.</p>		

	<p>Verify mac learning on FI server links after blade adapter firmware upgraded.</p> <p>Verify that no flooding happens after traffic convergence after blade adapter firmware upgraded.</p> <p>Verify that IGMP snooping is working as expected after blade adapter firmware upgraded.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption.</p>		
<p>UCS – Blade BIOS upgrade</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after blade BIOS upgraded.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after blade BIOS upgraded.</p> <p>Verify there is no mac address learning on FI uplink.</p> <p>Verify mac learning on FI server links after blade BIOS upgraded.</p> <p>Verify that no flooding happens after traffic convergence after blade BIOS upgraded.</p> <p>Verify that IGMP snooping is working as expected after blade BIOS upgraded.</p> <p>Verify DHCP/BOOTP functionalities.</p> <p>MEM and CPU:</p> <p>Monitor MEM and CPU Usage on FI.</p> <p>Convergence:</p> <p>Measure unicast/multicast traffic convergence for each disruption.</p>		
<p>UCS – VMotion</p>	<p>Verify FI uplink dynamic pinning works as expected.</p> <p>Verify that CDP/LLDP does not lose peer information for non-affected links. Verify that CDP/LLDP peer is removed for disrupted link.</p> <p>Verify SNMP traps are sent from FI to SNMP collector.</p> <p>Verify unicast and multicast traffic should re-converge after VMotion.</p> <p>Verify RPF check/ Déjà vu check/ Broadcast traffic pinning works as expected after VMotion.</p> <p>Verify there is no mac address learning on FI uplink.</p>		

Verify mac learning on FI server links after VMotion.		
---	--	--

Verify that no flooding happens after traffic convergence after VMotion.		
--	--	--

Verify that IGMP snooping is working as expected after VMotion.		
---	--	--

Verify DHCP/BOOTP functionalities.		
------------------------------------	--	--

MEM and CPU:		
--------------	--	--

Monitor MEM and CPU Usage on FI.		
----------------------------------	--	--

Convergence:		
--------------	--	--

Measure unicast/multicast traffic convergence for each disruption.		
--	--	--