illilli CISCO

Unified Communications System リリース 8.5 日本語版 テスト結果サマリ

18th Feb 2011

対象コンポーネント

| - | | | | |
|----------------------------------|-------------------------------------------------------|-----------|-------------------------|--|
| Category | Component | Version | | |
| Call Control | Cisco Unified Communications Manager | Version | 8.5.1.10000-26 | |
| | | Locale | JP(8.5.1.9902-56) | |
| | | Dial plan | dp-ffr.3-1-8.JP.cop.sgn | |
| | Cisco Unified Survivable Remote Site Telephony (SRST) | Version | 8.5 | |
| | | IOS | 15.1(3)T | |
| | Cisco Unified Communications Manager Express | Version | 8.5 | |
| | | IOS | 15.1(3)T | |
| | | Locale | JP (8.1.2.1) | |
| Applications | Cisco Unified Presence | Version | 8.5.1.10000-35 | |
| | | Locale | JP(8.5.1.9902-149) | |
| Voice Mail and Unified Messaging | Cisco Unity Connection | Version | 8.5.1.10000-26 | |
| | | Locale | JP(8.5.0.0-181) | |
| Endpoints and Clients | Cisco Unified IP Phones | | | |
| | SIP 3911 | | 8-1-2SR1 | |
| | 6921 | | 9-1-1-0 | |
| | 6941 | | 9-1-1-0 | |
| | 6961 | | 9-1-1-0 | |
| | 7961 | | 9-1-1SR1S | |
| | 7961G | | 9-1-1SR1S | |
| | 7975 | | 9-1-1SR1S | |
| | 7985 | | cmterm_7985.4-1-7-0 | |
| | 8961 | | sip8961.9-1-1 | |
| | 9951 | | sip9951.9-1-1 | |
| | 9971 | | sip9971.9-1-1 | |

8.5.1.17660

15.1(3)T

IE 8

IOS

Win-XP

8.5.98.16872

Windows XP - SP2 (Jap)

Cisco Unified Personal Communicator

Cisco IOS Voice and Data Gateways

Operating System

Browser


Cisco UC Integration for Microsoft Office Communicator

| Category | C | | |
|--------------|-------------------------------|--|--|
| Call Control | Cisco Unified Communication | | |
| | Cisco Unified Survivable Remo | | |


Communications Infrastructure

Client





テスト結果



未解決の障害①: Defect ID - CSCtk67772

Title: ETSGJ-CH:ICD states- disabled ,Not able to change the state(UCCX CAD)

Description: ICD states- disabled ,Not able to change the state(UCCX CAD)


Steps to reproduce:

- 1. Configure CAD Agent A
- 2. Login to CAD Agent A
- 3. Necessary configuration on UCCX, CUCM
- 4. Let A be in ready state
- 5. Let A get a call popup
- 6. Don't answer the call
- 7. After 2 minutes, call pop up goes off
- 8. Now the ICD state was Not ready
- 9. Change the State to Ready
- 10. Here All ICD state buttons gets disabled

Severity: Sev 2

Test Environment:

UCCX System version: 8.5.1.10000.37



未解決の障害②: Defect ID - CSCtk62187

Title: ETSGJ-CH:Unable to upload scripts through Application Wizard of UCCX

Description: Unable to upload scripts through Application Wizard of UCCX

Steps to reproduce:

- Cisco Unified CCX Administration page navigate to Wizard -> Application wizard -> Scripts -> Upload scripts
- 2. Click on Browse and choose a script to upload.
- 3. After clicking "upload" the page goes blank.

Severity: Sev 3

Work around:

Able to upload new scripts from the Applications -> Script management page.

Test Environment:

UCCX System version: 8.5.1.10000.37

