

Verifying that the Data Path is Ready

This chapter includes the following sections:

- Verifying that Dynamic vNICs Are Up and Running, page 1
- Verifying the Ethernet Data Path, page 2
- Verifying the Data Path for Fibre Channel Switch Mode, page 2

Verifying that Dynamic vNICs Are Up and Running

When you upgrade a Cisco UCS that includes dynamic vNICs and an integration with VMware vCenter, you must verify that all dynamic VNICs are up and running on the new primary fabric interconnect before you activate the new software on the former primary fabric interconnect to avoid data path disruption.

Perform this step in the Cisco UCS Manager GUI.

Procedure

- Step 1 In the Navigation pane, click VM.
- **Step 2** On the VM tab, expand All > VMware > Virtual Machines.
- **Step 3** Expand the virtual machine for which you want to verify the dynamic vNICs and choose a dynamic vNIC.
- **Step 4** In the Work pane, click the VIF tab.
- Step 5 On the VIF tab, verify that the Status column for each VIF is Online.
- **Step 6** Repeat Steps 3 through 5 until you have verified that the VIFs for all dynamic vNICs on all virtual machines have a status of **Online**.

1

Verifying the Ethernet Data Path

Procedure

	Command or Action	Purpose	
Step 1	UCS-A /fabric-interconnect # connect nxos {a b}	 Enters NX-OS mode for the fabric interconnect. Returns the number of active Ethernet interfaces. Verify that this number matches the number of Ethernet interfaces that were up prior to the upgrade. Returns the total number of MAC addresses. Verify that this number matches the number of MAC addresses prior to the upgrade. 	
Step 2	UCS-A(nxos)# show int br grep -v down wc –l		
Step 3	UCS-A(nxos)# show platform fwm info hw-stm grep '1.' wc –l		

The following example returns the number of active Ethernet interfaces and MAC addresses for subordinate fabric interconnect A so that you can verify that the Ethernet data path for that fabric interconnect is up and running:

```
UCS-A /fabric-interconnect # connect nxos a
UCS-A(nxos)# show int br | grep -v down | wc -l
86
UCS-A(nxos)# show platform fwm info hw-stm | grep '1.' | wc -l
80
```

Verifying the Data Path for Fibre Channel Switch Mode

For best results when upgrading a Cisco UCS domain, we recommend that you perform this task before you begin the upgrade and after you activate the subordinate fabric interconnect, and then compare the two results.

Procedure

	Command or Action	Purpose Enters NX-OS mode for the fabric interconnect.	
Step 1	UCS-A /fabric-interconnect # connect nxos {a b}		
Step 2	UCS-A(nxos)# show flogi database	Displays a table of flogi sessions.	
Step 3	UCS-A(nxos)# show flogi database grep –I fc wc –1	Returns the number of servers logged into the fabric interconnect.	
		The output should match the output you received when you performed this verification prior to beginning the upgrade.	

I

The following example displays the flogi-table and number of servers logged into subordinate fabric interconnect A so that you can verify that the Fibre Channel data path for that fabric interconnect in Fibre Channel End-Host mode is up and running:

```
UCS-A /fabric-interconnect # connect nxos a UCS-A(nxos)# show flogi database
```

INTERFACE	VSAN	FCID	PORT NAME	NODE NAME		
vfc726	800	0xef0003	20:00:00:25:b5:26:07:02	20:00:00:25:b5:26:07:00		
vfc728	800	0xef0007	20:00:00:25:b5:26:07:04	20:00:00:25:b5:26:07:00		
vfc744	800	0xef0004	20:00:00:25:b5:26:03:02	20:00:00:25:b5:26:03:00		
vfc748	800	0xef0005	20:00:00:25:b5:26:04:02	20:00:00:25:b5:26:04:00		
vfc764	800	0xef0006	20:00:00:25:b5:26:05:02	20:00:00:25:b5:26:05:00		
vfc768	800	0xef0002	20:00:00:25:b5:26:02:02	20:00:00:25:b5:26:02:00		
vfc772	800	0xef0000	20:00:00:25:b5:26:06:02	20:00:00:25:b5:26:06:00		
vfc778	800	0xef0001	20:00:00:25:b5:26:01:02	20:00:00:25:b5:26:01:00		
Total number of flogi = 8. UCS-A(nxos) # show flogi database grep fc wc -l 8						

٦